

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

22,902

1 LOCATION OF WATER WELL: County: Sedgwick Street/Rural Address of Well Location: if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 151st St. W. and 93rd St. N.		Fraction 1/4 1/4 1/4 SW 1/4		Section Number 23	Township No. T 25 S	Range Number R 2 ☐ E ☒ W																																																																		
2 WATER WELL OWNER: Tony Wilbur RR#, Street Address, Box #: 5009 Harborside City, State, ZIP Code : Wichita. KS 67204		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																						
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 210 ft. Depth(s) Groundwater Encountered (1) 40 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 800 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 30 in. to 210 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter .16 in. to .210 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface .12 in., Weight .16 lbs./ft., Wall thickness or gauge No. SCH40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 40 ft. to 210 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 210 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																								
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 3 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none-empty field Direction from well Distance from well																																																																								
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0'</td> <td>3'</td> <td>Topsoil</td> <td>140'</td> <td>160'</td> <td>Clay</td> </tr> <tr> <td>3'</td> <td>5'</td> <td>Fine Sand</td> <td>160'</td> <td>167'</td> <td>Clay</td> </tr> <tr> <td>5'</td> <td>40'</td> <td>Medium sand to Large gravel</td> <td>167'</td> <td>175'</td> <td>Clay</td> </tr> <tr> <td>40'</td> <td>50'</td> <td>Fine Sandy Clay</td> <td>175'</td> <td>180'</td> <td>Clay</td> </tr> <tr> <td>50'</td> <td>60'</td> <td>Clay</td> <td>180'</td> <td>210'</td> <td>Medium Sand</td> </tr> <tr> <td>60'</td> <td>80'</td> <td>Fine Sand</td> <td>210'</td> <td></td> <td>Shale</td> </tr> <tr> <td>80'</td> <td>100'</td> <td>Fine Sand with Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>100'</td> <td>125'</td> <td>Fine to Medium Sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>125'</td> <td>135'</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>135'</td> <td>140'</td> <td>Fine Sand</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0'	3'	Topsoil	140'	160'	Clay	3'	5'	Fine Sand	160'	167'	Clay	5'	40'	Medium sand to Large gravel	167'	175'	Clay	40'	50'	Fine Sandy Clay	175'	180'	Clay	50'	60'	Clay	180'	210'	Medium Sand	60'	80'	Fine Sand	210'		Shale	80'	100'	Fine Sand with Clay				100'	125'	Fine to Medium Sand				125'	135'	Clay				135'	140'	Fine Sand			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																			
0'	3'	Topsoil	140'	160'	Clay																																																																			
3'	5'	Fine Sand	160'	167'	Clay																																																																			
5'	40'	Medium sand to Large gravel	167'	175'	Clay																																																																			
40'	50'	Fine Sandy Clay	175'	180'	Clay																																																																			
50'	60'	Clay	180'	210'	Medium Sand																																																																			
60'	80'	Fine Sand	210'		Shale																																																																			
80'	100'	Fine Sand with Clay																																																																						
100'	125'	Fine to Medium Sand																																																																						
125'	135'	Clay																																																																						
135'	140'	Fine Sand																																																																						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 07/06/2013 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 07/08/2013 under the business name of Premier Pump & Well Service Inc. by (signature) [Signature]																																																																								
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send one copy to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-3524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html																																																																								