

1 LOCATION OF WATER WELL:		WATER WELL RECORD FORM WITH 3 HOLE SLITS		Section Number		Township Number		Range Number			
County: Sedgwick		NE 1/4 NW 1/4 NW 1/4		1		T 25 S		R 2 XW			
Distance and direction from nearest town or city street address of well if located within city?											
4 miles west of Sedgwick, KS											
2 WATER WELL OWNER: Mike Sharp											
RR#, St. Address, Box # : c/o Jerry Morris, Rt. 2						Board of Agriculture, Division of Water Resources					
City, State, ZIP Code : Sedgwick, KS 67135						Application Number: N/A					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION:								
			Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.								
			WELL'S STATIC WATER LEVEL 32 ft. below land surface measured on mo/day/yr 7/18/98								
			Pump test data: Well water was ft. after hours pumping gpm								
			Est. Yield 20-50 gpm: Well water was ft. after hours pumping gpm								
			Bore Hole Diameter 9 in. to 60 ft., and in. to ft.								
			WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well								
			☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)								
			2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well								
			Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒ ; If yes, mo/day/yr sample was submitted								
			Water Well Disinfected? Yes ☒ No								
5 TYPE OF BLANK CASING USED:											
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped											
☒ PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded											
7 Fiberglass Threaded											
Blank casing diameter 5 in. to 50 ft. Dia. in. to ft. Dia. in. to ft.											
Casing height above land surface 12 in., weight 2.37 lbs./ft. Wall thickness or gauge No. 214											
TYPE OF SCREEN OR PERFORATION MATERIAL: ☒ PVC 10 Asbestos-cement											
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)											
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)											
SCREEN OR PERFORATION OPENINGS ARE:											
1 Continuous slot ☒ Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)											
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes											
7 Torch cut 10 Other (specify)											
SCREEN-PERFORATED INTERVALS: From 50 ft. to 60 ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
GRAVEL PACK INTERVALS: From 20 ft. to 60 ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other											
Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.											
What is the nearest source of possible contamination:											
1 Septic tank ☒ Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well											
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well											
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)											
13 Insecticide storage											
Direction from well? South How many feet? 100											
FROM		TO		LITHOLOGIC LOG		FROM		TO		PLUGGING INTERVALS	
0		2		Topsoil							
2		15		Brown Sandy clay							
15		48		Medium to Coarse gray Sand							
48		53		Coarse Gray Sand with clay layers							
53		60		Medium to coarse gray sand							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/18/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 8/5/98 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>											
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.											