


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

C W12

1. Location of well:		County <u>Sedgwick</u>	Fraction center of <u>SW 1/4 of NW 1/4</u>	Section number <u>2</u>	Township number <u>25</u>	Range number <u>2</u>	E (W)
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1 1/2 N Bentley</u>				3. Owner of well: <u>Melvin Broadhurst</u> R.R. or street: City, state, zip code: <u>Valley Center, Kansas 67147</u>			
4. Locote with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>5/1/78</u> Well depth <u>117</u> ft.			
N 1 Mile W E S 1 Mile				open field			
5. Type and color of material				From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
<u>Topsoil</u>				<u>0</u>	<u>1</u>	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
<u>Fine Sand - some clay</u>				<u>1</u>	<u>26</u>	9. Casing: Material <u>C-Asb</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>18</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>16</u> in. to <u>117</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>3/4</u>	
<u>Sand mixed with clay</u>				<u>26</u>	<u>54</u>	10. Screen: Manufacturer's name <u>Johnson</u> Type <u>Cement-Asbestos</u> Dia. <u>16"</u> Slot/gauze <u>1/4"</u> Length <u>39'</u> Set between <u>65</u> ft. and <u>117</u> ft. <u>65</u> ft. and <u>91</u> ft. Gravel pack? ☒ Size range of material <u>3/8</u>	
<u>Clay</u>				<u>54</u>	<u>65</u>	11. Static water level: <u>15</u> ft. below land surface Date <u>4/20/78</u>	
<u>Med. Gravel</u>				<u>65</u>	<u>91</u>	12. Pumping level below land surfaces: <u>24</u> ft. after <u>1</u> hrs. pumping <u>800</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1000</u> g.p.m.	
<u>Clay</u>				<u>91</u>	<u>104</u>	13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No Date <u> </u>	
<u>Good Gravel</u>				<u>104</u>	<u>117</u>	14. Well head completion: <u> </u> Pitless adapter <u>18</u> inches above grade	
						15. Well grouted? ☒ With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u> </u> ft. to <u> </u> ft.	
						16. Nearest source of possible contamination: <u>none</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No	
						17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless</u> Model number <u>8273</u> HP <u>60</u> Volts <u> </u> Length of drop pipe <u>65</u> ft. capacity <u>850</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other	
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irrigation 238</u> Business name <u>Maize</u> License No. <u> </u> Address <u> </u> Signed <u>Kathleen Weninger</u> Date <u>6/27/78</u> Authorized representative	
18. Elevation:		19. Remarks: <u>customer did cement</u>					
Topography: <u> </u> Hill <u> </u> Slope ☒ Upland <u> </u> Valley							

25-2-W-2-C514

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5