

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

C W 12

1. Location of well:		County Sedgwick	Fraction center of SW 1/4 NW 1/4 NW 1/4 SW 1/4	Section number 6	Township number T 25 S R 2 E (W)	Range number 2
2. Distance and direction from nearest town or city: Street address of well location if in city: 1 N. 4 W. 1/2 N. Bentley			3. Owner of well: Don Broadhurst R.R. or street: RFD 2 City, state, zip code: Sedgwick, Ks. 67135			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 5/10/80 Well depth 54 ft.		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Topsoil		0		1		9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 54 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 34
Fine sand		1		15		10. Screen: Manufacturer's name Johnson Type Cement-Asb Dia. 16 " Slot/gauze 44 " Length 13 " Set between 41 ft. and 54 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 3/8
Clay		15		19		11. Static water level: ☐ mo./day/yr. 14 ft. below land surface Date 5/10/80
Small Gravel		19		37		12. Pumping level below land surfaces: 23 ft. after 2 hrs. pumping 200 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 800 g.p.m.
Clay		37		40		13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.
Medium Gravel		40		54		14. Well head completion: ☐ Pitless adapter 12 inches above grade
						15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: None ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No
						17. Pump: ☐ Not installed Manufacturer's name Peerless Model number 8942 HP 40 Volts ☐ Length of drop pipe 45 ft. capacity 250 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize, Ks. 67101 License No. ☐ Address Maize, Ks. 67101 Signed H. Weninger Date 6/12/80 Authorized representative
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5