


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 NE 1/4	Section number 10	Township number T 25 S	Range number R 2 E
2. Distance and direction from nearest town or city: Street address of well location if in city: 1/2 N 1/2 W Bentley				3. Owner of well: Reinard Simon R.R. or street: City, state, zip code: Colwich Kansas 67030		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile				Sketch map: 		
5. Type and color of material				From	To	6. Bore hole dia. 30 in. Completion date 7/17/76 Well depth 85 ft.
Topsoil				0	1	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
Fine Sand				1	20	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Fine Sand w/Clay				20	35	9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia 16 in. to 85 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4"
Good Gravel				35	45	10. Screen: Manufacturer's name Johnson Type Cem-Asb Dia. 16" Slot/gauze 1/4" Length 39' Set between 59 ft. and 85 ft. 33 ft. and 46 ft. Gravel pack? Yes Size range of material 3/8
Clay				45	60	11. Static water level: ☐ mo./day/yr. 18 ft. below land surface Date 6/25/76
Good Gravel				60	85	12. Pumping level below land surfaces: 25 ft. after 1 hrs. pumping 900 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1000 g.p.m.
						13. Water sample submitted: ☐ Yes ☒ No Date ☐
						14. Well head completion: ☐ Pitless adapter 18 inches above grade
						15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: ft. 44m Direction W Type Dom Well disinfected upon completion? ☐ Yes ☒ No
						17. Pump: ☐ Not installed Manufacturer's name Peerless Model number G1 3915 HP ☐ Volts ☐ Length of drop pipe 70 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Drilling 238 Business name Maize License No. ☐ Address Weninger Signed Weninger Date 7/23/76 Authorized representative						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3