

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

C N/2

1. Location of well:		County <u>Sedgwick</u>	Fraction <u>center of</u> <u>E 1/4 NW 1/4 W 1/4 NE 1/4</u>	Section number <u>13</u>	Township number <u>25</u>	Range number <u>2</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1 1/2 E Bentley</u>			3. Owner of well: <u>Noel Ramsey</u> R.R. or street: <u>Rt. 1</u> City, state, zip code: <u>Sedgwick, Ks. 67135</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>7/13/79</u> Well depth <u>104</u> ft.		
		open field		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Topsoil		0		1		9. Casing: Material <u>C-Asb</u> Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>16</u> in. to <u>104</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>314</u>
Fine Sand		1		15		10. Screen: Manufacturer's name <u>Johnson</u> Type <u>Cement-Asb</u> Dia. <u>16</u> " Slot/gauze <u>1/4</u> " Length <u>39</u> " Set between <u>52</u> ft. and <u>65</u> ft. <u>78</u> ft. and <u>104</u> ft. Gravel pack? ☒ Size range of material <u>3/8</u>
Med. Sand Clay		15		22		11. Static water level: <u>18</u> ft. below land surface Date <u>7/6/79</u> <u>18</u> ft. below land surface Date <u>7/6/79</u>
Med. Sand		22		35		12. Pumping level below land surfaces: <u>26</u> ft. after <u>1</u> hrs. pumping <u>600</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1200</u> g.p.m.
Clay		35		50		13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No Date <u> </u>
Med. Gravel		50		65		14. Well head completion: <u>12</u> inches above grade <u> </u> Pitless adapter <u>12</u> inches above grade
Clay		65		75		15. Well grouted? ☒ With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
Gravel-good		75		104		16. Nearest source of possible contamination: <u>None</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No
(Use a second sheet if needed)						17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless</u> Model number <u>8937</u> HP <u>50</u> Volts <u> </u> Length of drop pipe <u>70</u> ft. capacity <u>900</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irrigation</u> Business name <u>Maize, Ks. 67101</u> License No. <u>238</u> Address <u>Maize, Ks. 67101</u> Signed <u>Kathleen Weninger</u> Date <u>12/30/79</u> Authorized representative			
Topography: <u> </u> Hill <u> </u> Slope ☒ Upland <u> </u> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5