


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction SW 1/4 SW 1/4 NE 1/4	Section number 15	Township number T 25 S	Range number R 2 W E/W
2. Distance and direction from nearest town or city: 1/2 SO - 1/2		3. Owner of well: T.C. DARTER				
Street address of well location if in city: West of Bentley Ks		R.R. or street: R.R.				
		City, state, zip code: SEDGWICK KS 67135				
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 5-21 Well depth 52 ft. 77		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
TOP SOIL		0	2	9. Casing: Material IRON Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight 32 lbs./ft. Dia. 16 in. to 52 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4"		
CLAY - SANDY		2	6	10. Screen: Manufacturer's name BUROA TILE CO. Type TRANSITE Dia. 16" I.P. Slot/gauze 1/8 Length 26 Set between 26 ft. and 52 ft. ☐ ft. and ☐ ft.		
GRAVEL - COARSE		6	31	Gravel pack? ☒ Size range of material 1/4"		
SAND - MED.		31	38	11. Static water level: ☐ mo./day/yr. 8 ft. below land surface Date 5-21-77		
CLAY - BLUE		38	52	12. Pumping level below land surfaces: 16 ft. after 1 hrs. pumping 600 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 800 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: ☐ Pitless adapter ☐ Inches above grade		
				15. Well grouted? yes Puddled clay With: ☐ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: ft. 1000 Direction N Type Well Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PETERSON TOOL INC 138A Business name License No. Address Box 150 Lindsborg, KS Signed Wallace Peterson Date 6-3 Authorized representative 77		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5