

1 LOCATION OF WATER WELL		Fracture XXXX	Section Number	Township Number	Range Number		
County: Sedgwick		NW, 1/4 NE 1/4 NE 1/4	217	T 25 South	R 2 West EW		
Distance and direction from nearest town or city? 4 mile E Mt. Hope Rd, 1 S, 1 3/4 E, south by road.			Street address of well if located within city? 2 m W of Bentley Dr				
2 WATER WELL OWNER: Larry Williams (Well # 7)							
RR#, St. Address, Box #: Bank of Halstead							
City, State, ZIP Code: Halstead, KS 67056							
Board of Agriculture, Division of Water Resources Application Number: 29,973 DP							
3 DEPTH OF COMPLETED WELL: 45 ft. Bore Hole Diameter: 28 in. to 45 ft., and in. to ft.							
Well Water to be used as:							
1 Domestic		3 Feedlot	5 Public water supply	8 Air conditioning	11 Injection well		
2 Irrigation		4 Industrial	6 Oil field water supply	9 Dewatering	12 Other (Specify below)		
XX			7 Lawn and garden only	10 Observation well			
Well's static water level: 11' ft. below land surface measured on 10 month 6 day 1980 year							
Pump Test Data: Well water was: XXX 26' 8" after 1 hours pumping 1300 gpm							
Est. Yield 1300 gpm: Well water was 23' 8" ft. after 2 hours pumping 1000 gpm							
4 TYPE OF BLANK CASING USED:							
XX Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	Casing Joints: Glued Clamped		
2 PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded XX		
			7 Fiberglass		Threaded		
Blank casing dia 16 in. to 0 ft., Dia 16 in. to 30 ft., Dia in. to ft.							
Casing height above land surface 12 in., weight 50 lbs./ft. Wall thickness or gauge No 7							
TYPE OF SCREEN OR PERFORATION MATERIAL:							
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)		
2 Brass		XX Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)		
Screen or Perforation Openings Are:							
1 Continuous slot		3 Mill slot	XX Wire wrapped	8 Saw cut	11 None (open hole)		
2 Louvered shutter		4 Key punched	7 Torch cut	9 Drilled holes			
Screen-Perforation Dia 16 in. to 30 ft., Dia 16 in. to 45 ft., Dia in. to ft.							
Screen-Perforated Intervals: From 30 ft. to 45 ft., From ft. to ft., From ft. to ft.							
Gravel Pack Intervals: From 10 ft. to 45 ft., From ft. to ft., From ft. to ft.							
5 GROUT MATERIAL: XX Neat cement 2 Cement grout 3 Bentonite 4 Other							
Grouted Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.							
What is the nearest source of possible contamination:							
1 Septic tank		4 Cess pool	7 Sewage lagoon	10 Fuel storage	14 Abandoned water well		
2 Sewer lines		5 Seepage pit	8 Feed yard	11 Fertilizer storage	15 Oil well/Gas well		
3 Lateral lines		6 Pit privy	9 Livestock pens	12 Insecticide storage	16 Other (specify below)		
				13 Watertight sewer lines	none		
Direction from well: How many feet: ? Water Well Disinfected? Yes No XX							
Was a chemical/bacteriological sample submitted to Department? Yes XXXXXX NO No XX If yes, date sample was submitted XXXXXX month XXXXX day 1981 year Pump Installed? Yes X No							
If Yes: Pump Manufacturer's name: Western Land Roller Model No. 1 Stage 12 BH HP 25 Volts							
Depth of Pump Intake ft. Pumps Capacity rated at gal./min.							
Type of pump: 1 Submersible XX Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other							
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was XX constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 3 month 23 day XXXX 1981 year							
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134							
This Water Well Record was completed on 3 month 23 day 1981 year under the business name of Rosencrantz-Bemis Ent. by (signature) Mike Flowers							
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	5	Top Soil			
		5	13	Medium sand, loose formation, took water			
		13	14	Clay break			
		14	45	Medium sand & gravel, loose formation, took lots of water.			
ELEVATION:							
Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)							
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.							

OFFICE USE ONLY

T

R

EW

SEC.

NW 1/4 NE 1/4 SE 1/4