


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Sedgwick	Township name Eagle	Fraction center of SW 1/4	Section number 23	Town number T25 S	Range number R2 W		
Distance and direction from nearest town or city: 1 3/4 m. S. Bentley			3 Owner of well: Phil Dosien					
Street address of well location if in city:			Address: Rt. 2 Sedgwick Kansas					
Locate with "X" in section below: N  W S 1 Mile			Sketch map: open field			4 Well depth: 40 ft. Date of completion 4/3/76 Well diameter 30 in.		
2 Type and color of material			From	To	5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
			Topsoil		0	1	6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well	
			Fine sand		1	10	7 Casing: Material C-A Height: above/below Threaded ☐ Welded ☐ Surface 70 in. Diam. _____ Weight _____ lbs./ft. _____ 16 in. to 40 ft. depth Drive shoe? ☐ Yes ☐ No _____ in. to _____ ft. depth	
			Fine sand w/gray clay		10	20	8 Screen: Manufacturer Johnson Type Cem-Asb Dia. 16" Slot/gauze 1/4" Length 13' Set between 27 ft. and 40 ft. _____ Fittings: Gravel pack ☒ Yes ☐ No Size range of material 3/8	
			Gravel - fine to medium		20	40	9 Static water level: 20 ft. below land surface Date 4/3/76	
					10 Pumping level below land surfaces: 25 ft. after 1 hrs. pumping 700 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 750 g.p.m.			
					11 Water sample submitted: ☐ Yes ☒ No Date _____			
					12 Well head completion: ☐ Pitless adapter 10 inches above grade			
					13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ _____ Depth: From 0 ft. to 10 ft.			
					14 Nearest source of possible contamination: ft. 1400 Direction SE Type Dom. well Well disinfected upon completion? ☐ Yes ☒ No			
					15 Pump: ☐ Not installed Manufacturer's name Peerless Model number 3829 HP _____ Volts _____ Length of drop pipe 30 ft. capacity _____ g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
16 Remarks: elevation			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name _____ License No. _____ Address Maize, Kansas Signed R. Weninger Date 4/10/76 Authorized representative					

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5