

1 LOCATION OF WATER WELL		Fraction		Section Number		Township Number		Range Number	
County: Sedgwick		NW 1/4 NE 1/4 NW 1/4		26		T 25 S		R 2 E/W	
Distance and direction from nearest town or city? 2 miles south and 1/4 mile east of Bently, KS				Street address of well if located within city?					
2 WATER WELL OWNER:		Noel Ramsey							
RR#, St. Address, Box # :		Bently, KS 67106							
City, State, ZIP Code :		Bently, KS 67106							
3 DEPTH OF COMPLETED WELL		175 ft.		Bore Hole Diameter		24 in.		175 ft.	
Well Water to be used as:		5 Public water supply		8 Air conditioning		11 Injection well			
1 Domestic 3 Feedlot		6 Oil field water supply		9 Dewatering		12 Other (Specify below)			
2 Irrigation 4 Industrial		7 Lawn and garden only		10 Observation well					
Well's static water level		14 1/2 ft. below land surface measured on		11 month		24 day		1980 year	
Pump Test Data not ok'd :		Well water was		ft. after		hours pumping		gpm	
Est. Yield XXXXXXXX gpm:		Well water was		ft. after		hours pumping		gpm	
4 TYPE OF BLANK CASING USED:		5 Wrought iron		8 Concrete tile		Casing Joints: Glued		Clamped	
1 Steel		3 RMP (SR)		6 Asbestos-Cement		9 Other (specify below)		Welded XX	
2 PVC		4 ABS		7 Fiberglass				Threaded	
Blank casing dia		16 in.		75 ft.		Dia		in.	
Casing height above land surface		12 in.		weight 31.75		lbs./ft.		Wall thickness or gauge No. 188	
TYPE OF SCREEN OR PERFORATION MATERIAL:		1 Steel		3 Stainless steel		5 Fiberglass		8 RMP (SR)	
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS		12 None used (open hole)	
Screen or Perforation Openings Are:		1 Continuous slot		3 Mill slot		5 Gauzed wrapped		8 Saw cut	
2 Louvered shutter		4 Key punched		7 Torch cut		10 Other (specify) Doerr Bridge Slot		11 None (open hole)	
Screen-Perforation Dia		16 in.		175 ft.		Dia		in.	
Screen-Perforated Intervals:		From 75 ft.		to 175 ft.		From		ft. to	
Gravel Pack Intervals:		From 49 ft.		to 175 ft.		From		ft. to	
Annular fill		From 10 ft.		to 40 ft.		From		ft. to	
5 GROUT MATERIAL:		1 Neat cement		2 Cement grout		3 Bentonite		4 Other	
Grouted Intervals: From		0 ft.		to 10 ft.		From 40 ft.		to 49 ft.	
What is the nearest source of possible contamination:		1 Septic tank		4 Cess pool		7 Sewage lagoon		10 Fuel storage	
2 Sewer lines		5 Seepage pit		8 Feed yard		12 Insecticide storage		14 Abandoned water well	
3 Lateral lines		6 Pit privy		9 Livestock pens		13 Watertight sewer lines		15 Oil well/Gas well	
Direction from well		all		How many feet		n/a		Water Well Disinfected? Yes	
Was a chemical/bacteriological sample submitted to Department? Yes		No		XX		If yes, date sample			
was submitted		month		day		year		Pump Installed? Yes	
If Yes: Pump Manufacturer's name		Peerless Pump Co.		Model No.		12MB-2		HP 40	
Depth of Pump Intake		100 ft.		Pumps Capacity rated at		1200		gal./min.	
Type of pump:		1 Submersible		2 Turbine		3 Jet		4 Centrifugal	
		5 Reciprocating		6 Other					
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 11 month 24 day 1980 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on 4 month 21 day 1981 by (signature) Clarke Well & Eq., Inc.									
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM		TO		LITHOLOGIC LOG		FROM	
		0		3		Topsoil		86	
		3		37		Med. sand & gravel		92	
		37		50		Sandy clay/fine sand strk		115	
		50		53		Sandy clay, fine sand & gravel		126	
		53		58		V. fine-fine sand & gravel		129	
		58		69		Orange & tan sandy clay		160	
		69		75		V. fine-fine sand & grvl		164	
		75		78		F. sand w/stks sandy clay		177	
		78		81		Tan sandy clay			
		81		83		Fine sand & gravel			
		83		86		Tan sandy clay			
ELEVATION: unknown									
Depth(s) Groundwater Encountered		1. 14 1/2 ft.		2. ft.		3. ft.		4. ft.	
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.									