

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction SE 1/4 SE 1/4 SE 1/4 Section Number 6 Township Number T 25 S Range Number R 20 *AW*  
 COUNTY: EDWARDS  
 Distance and direction from nearest town or city street address of well if located within city?  
 FROM OPFERLE - 1/8 MILE EAST AND 1/2 MILE NORTH

2 WATER WELL OWNER: ACKERMAN, JERRY  
 RR#, St. Address, Box #: ROUTE #1 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: OPFERLE, KS 67563- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 204 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr 01/16/96  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 45 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 10 in. to 204 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOED  
 Blank casing diameter 5 in. to 204 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 80 ft. to 100 ft., From 0 ft. to 0 ft.  
 From 160 ft. to 200 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 35 ft. to 204 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 5 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: WATER TIGHT SEW.  
 Direction from well? EAST How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	60	CLAY			
60	75	CLAY CALACHIE ROCK			
75	90	CALACHIE FINE - MED SAND			
90	120	TAN IN COLOR CLAY			
120	160	GRAY CLAY			
160	220	SANDSTONE			
220	240	SANDSTONE CLAY LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 01/22/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 01/30/96 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Jessie Cuit*