

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: EDWARDS SW 1/4 SW 1/4 SW 1/4 22 T 25 S R 20 **XW**

Distance and direction from nearest town or city street address of well if located within city?
 FROM OFFERLE - 3 MILES SOUTH & 2 MILES EAST

2 WATER WELL OWNER: SEMKAN GAS PLANT
 RR#, St. Address, Box #: RR #1 -- BOX 18 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: OFFERLE, KS 67563- Application Number: EDWW 3043

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

<table border="1" style="border-collapse: collapse; width: 100%; height: 100%;"> <tr> <td style="width: 25%;"></td> <td style="width: 25%; text-align: center;">NW</td> <td style="width: 25%;"></td> <td style="width: 25%; text-align: center;">NE</td> </tr> <tr> <td style="text-align: center;">W</td> <td style="width: 25%;"></td> <td style="width: 25%;"></td> <td style="text-align: center;">E</td> </tr> <tr> <td style="text-align: center;">S</td> <td style="text-align: center;">SW</td> <td style="text-align: center;">SE</td> <td style="text-align: center;">NE</td> </tr> </table>		NW		NE	W			E	S	SW	SE	NE	<p>4 DEPTH OF COMPLETED WELL 225 ELEVATION: 0</p> <p>Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.</p> <p>WELL'S STATIC WATER LEVEL 61 ft. below land surface measured on mo/day/yr 04/27/05 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm</p> <p>Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm</p> <p>Bore Hole Diameter 10 in. to 225 ft., and in. to 0 ft.</p> <p>WELL WATER TO BE USED AS: DOMESTIC</p> <p>Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes</p>
	NW		NE										
W			E										
S	SW	SE	NE										

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 225 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 225 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY 35 CALACHIE			
20	40	14 WHITE CLAY 02 PINE SAND			
40	60	02 PINE SAND 16 GRAY CLAY			
60	80	32 TAN CLAY 16 GRAY CLAY			
80	100	16 GRAY CLAY 26 RED CLAY			
100	120	16 GRAY CLAY 26 RED CLAY 29 SANDSTONE			
120	140	29 SANDSTONE			
140	160	29 SANDSTONE			
160	180	29 SANDSTONE			
180	220	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/13/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Jubid Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: EDWARDS SW 1/4 SW 1/4 SW 1/4 22 T 25 S R 20 ~~B~~W

2 WATER WELL OWNER: SENKAN GAS PLANT
RR#, St. Address, Box #: RR #1 -- BOX 18 Board of Agriculture, Division of Water Resources
City, State, ZIP code : OFFERLE, KS 67563- Application Number: BDWW 3043

FROM	TO	LITHOLOGIC LOG
220	240	26 RED CLAY 16 GRAY CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/13/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Julie Creek*