

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SE 1/4 SE 1/4 25 T 25 S R 22 *W 28*

Distance and direction from nearest town or city street address of well if located within city?
 FROM SPEARVILLE - 1/2 SOUTH AND 4 EAST ON FOOTHILL ROAD

2 WATER WELL OWNER: INDICK, ANTHONY Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: 12994 FOOTHILL ROAD Application Number:
 City, State, ZIP code: SPEARVILLE, KS 67876-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 225 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 97 ft. below land surface measured on mo/day/yr 03/18/97
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 225 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 225 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 0 ft. to 0 ft.
 From 200 ft. to 220 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 80 ft. to 225 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 80 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: LIVESTOCK PENS
 Direction from well? NORTH How many feet? 110

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY CALACHIE FINE SAND			
40	55	FINE SAND ROCK LAYERS			
55	65	FINE - MED SAND VERY LOOSE			
65	80	ROCK LAYERS CLAY BLUE SHALE			
80	160	SANDSTONE			
160	180	SANDSTONE TAN IN COLOR SANDSTONE			
180	200	TAN IN COLOR SANDSTONE CLAY			
200	220	TAN IN COLOR SANDSTONE			
220	240	SANDSTONE CLAY LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 04/10/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 04/21/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Janice Crick*

(Continued)

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SE 1/4 SE 1/4 25 T 25 S R 22 E

2 WATER WELL OWNER: INDICK, ANTHONY Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: 12994 FOOTHILL ROAD Application Number:
 City, State, ZIP code: SPEARVILLE, KS 67876-

FROM	TO	LITHOLOGIC LOG
240	280	CLAY LAYERS SANDSTONE