

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 029 FORD SE 1/4 SE 1/4 SW 1/4 21 T 25 S R 23 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5 MILES WEST OF SPEARVILLE.

2 WATER WELL OWNER: JOHN STEGMAN Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: Application Number:
 City, State, ZIP code : SPEARVILLE, KS 67876-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 187 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 40 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr 08/29/91
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 12 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9.875 in. to 187 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 187 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 12 ft. to 13 ft., From 0 ft. to 0 ft.
 From 167 ft. to 187 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 22 ft. to 60 ft., From 0 ft. to 0 ft.
 From 70 ft. to 187 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 22 ft., From 60 ft. to 70 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	9	31 CALICHE			
9	44	23 SANDSTONE 01 CLAY 20 LIMESTONE			
44	56	19 SHALE			
56	65	19 SHALE			
65	76	19 SHALE 20 LIMESTONE 23 SANDSTONE			
76	84	23 SANDSTONE			
84	116	19 SHALE 20 LIMESTONE 23 SANDSTONE			
116	124	19 SHALE 23 SANDSTONE			
124	159	19 SHALE 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/30/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas B. Henkle

