

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction *SW 1/4 NW 1/4 SW 1/4* Section Number 36 Township Number T 25 S Range Number R 25 W
 COUNTY: FORD

Distance and direction from nearest town or city street address of well if located within city?
 LOT 22 - BLOCK 1

2 WATER WELL OWNER: DAILY, BOB
 RR#, St. Address, Box #: 1812 MANOR DRIVE
 City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

| | | |
|------------------|----|----|
| 1 | NW | NE |
| M i l e | W | E |
| | SW | SE |

4 DEPTH OF COMPLETED WELL 80 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 45 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 80 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 80 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 55 ft. to 75 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 26 ft. to 80 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 26 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

| FROM | TO | LITHOLOGIC LOG | FROM | TO | PLUGGING INTERVALS |
|------|----|--|------|----|--------------------|
| 0 | 3 | TOPSOIL | | | |
| 3 | 20 | CLAY CALACHIE | | | |
| 20 | 42 | CALACHIE LIMESTONE IN LAYERS | | | |
| 42 | 60 | FINE - MED SAND GRAVEL SAND ROCK LAYER | | | |
| 60 | 77 | MED-COARSE SAND GRAVEL VERY LOOSE | | | |
| 77 | 80 | CLAY BLUE SHALE | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/14/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/14/96 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*