

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 NW 1/4 SE 1/4 36 T 25 S R 25 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY, KS. - 3 MILES NORTH ON AVE. A

2 WATER WELL OWNER: HILL, RAYFORD Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: ROUTE #2 Application Number:
 City, State, ZIP code: DODGE CITY, KS 67801-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 100 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1	---	NW	---	NE	---
W	---		---		E
1	---		---		E
1	---		---		E
e	---	SW	X	SE	---

WELL'S STATIC WATER LEVEL 47 ft. below land surface measured on mo/day/yr 10/24/94
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 125 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 12 in. to 100 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 9 in. to 100 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 50 ft. to 90 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 24 ft. to 100 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 4 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: POND
 Direction from well? NORTHEAST How many feet? 175

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL BROWN CLAY			
20	41	BROWN CLAY CALACHIE			
41	52	MEDIUM SAND GRAVEL			
52	53	ROCK LAYERS			
53	75	COARSE SAND GRAVEL			
75	77	YELLOW CLAY			
77	100	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/26/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/02/94 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*