

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 029 FORD | NE 1/4 SE 1/4 SW 1/4 | 30 | T 25 S | R 26 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 1/2 N, 1/2 W, 1 N, 1 1/2 W, 1/4 N OF HOWELL

2 WATER WELL OWNER: T. BOGNER FARMS
 RR#, St. Address, Box #: 10055 EAGLE ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number: 41,526

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 240 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \					WELL'S STATIC WATER LEVEL 116 ft. below land surface measured on mo/day/yr 12/11/95
					Pump test data: Well water was 160 ft. after 4 hours pumping 578 gpm
1	NW		NE		Estimated Yield 550 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
M					Bore Hole Diameter 24 in. to 240 ft., and in. to 0 ft.
i	W			E	WELL WATER TO BE USED AS: 02 IRRIGATION
l					Was a chemical/bacteriological sample submitted to department? No ;
e					If yes, mo/day/yr sample was submitted Water well disinfected? Yes
\ /					

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 240 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.
 From 171 ft. to 231 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 240 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	40	01 CLAY 31 CALICHE			
40	90	31 CALICHE 01 CLAY 05 SAND			
90	120	05 SAND 01 CLAY			
120	140	05 SAND 31 CALICHE			
140	160	05 SAND 31 CALICHE			
160	171	01 CLAY 31 CALICHE			
171	180	05 SAND 01 CLAY			
180	200	05 SAND 01 CLAY			
200	210	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/07/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/21/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 029 FORD | NE 1/4 SE 1/4 SW 1/4 | 30 | T 25 S | R 26 W

2 WATER WELL OWNER: T. BOGNER FARMS
RR#, St. Address, Box # : 10055 EAGLE ROAD Board of Agriculture, Division of Water Resources
City, State, ZIP code : DODGE CITY, KS 67801- Application Number:

FROM	TO	LITHOLOGIC LOG
210	230	05 SAND 01 CLAY
230	240	19 SHALE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/07/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/21/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichmuth