

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.


Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

ACK

DODGE CITY NW

1 Location of well:	County <b>Ford</b>	Township name <b>Royal</b>	Fraction <b>SW SW NE</b> <b>SW 1/4 of NE 1/4</b>	Section number <b>1</b>	Town number <b>T-25-S</b>	Range number <b>R-26-W</b>
---------------------	-----------------------	-------------------------------	--	----------------------------	------------------------------	-------------------------------

Distance and direction from nearest town or city: <b>4 1/2 mi. West and 8 1/2 north of Dodge City</b>	3 Owner of well: <b>Harold Rebein</b>
Street address of well location if in city:	Address: <b>Dodge City, Kansas</b>

Locate with "X" in section below: 	Sketch map:	4 Well depth: <b>420</b> ft. Date of completion <b>10-15-75</b> Well diameter <b>28</b> in.
		5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
		6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well
		7 Casing: Material <b>Metal</b> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. Diam. Weight <b>37</b> lbs./ft. <b>1</b> <b>16</b> in. to <b>420</b> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

2	Type and color of material	From	To
	Surface	0	3
	Clay and rock layers	3	63
	Gray and blue shale with rock layers	63	212
	A-1 tan and brown sandstone	212	282
	Gray shale	282	303
	Tan sandstone	303	308
	Shale	308	310
	Tan sandstone	310	315
	Shale	315	330
	Good brown sandstone	330	361
	Shale	361	365
	Good tan and brown sandstone	365	418
	Shale	418	430
	<b>Block 63</b>		
	(use a second sheet if needed)		

8 Screen: Manufacturer <b>WA Brown</b> Type <b>Free-flow</b> Dia. <b>16</b> slot Slot/gauge <b>1/8</b> length <b>2</b> Set between <b>400</b> ft. and <b>420</b> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/2</b> in.	9 Static water level: <b>NA</b> _____ ft. below land surface Date _____
10 Pumping level below land surfaces: <b>340</b> ft. after <b>10</b> hrs. pumping <b>1050</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>1050</b> g.p.m.	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____
12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade	13 Well grouted? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From _____ ft. to _____ ft.
14 Nearest source of possible contamination: ft. <b>1200</b> Direction <b>N</b> Type <b>well</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other

16 Remarks: elevation  Topography: <b>no water level</b> <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley <b>1010</b>	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Ace-Hi International Inc.</b> Business name <b>Dodge City, Kansas</b> License No. _____ Address <b>Dodge City, Kansas</b> Signed <b>Gaul G. Little</b> Date <b>10-24-75</b> Authorized representative
---	--