

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 SW 1/4	16	T 25 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?
FROM CIMARRON - 1 MILE ON HIGHWAY 23 - 2 1/2 E, 3 N & 1/2 E.

2 WATER WELL OWNER:	NIEMIER, FLORA MRS.	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	8 NATHAN ENGLISH	Application Number:
City, State, ZIP code :	CIMARRON, KS 67835-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 218 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
	WELL'S STATIC WATER LEVEL 110 ft. below land surface measured on mo/day/yr 03/18/97 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 218 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 218 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT	

SCREEN PERFORATED INTERVALS:	From 176 ft. to 214 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 30 ft. to 218 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE	
Grout Intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: ABANDONED WELL	
Direction from well? SOUTH	How many feet? 20

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY FINE SAND			
40	60	FINE SAND CLAY			
60	80	CLAY LIMESTONE ROCK LAYERS			
80	100	FINE - MED SAND LIMESTONE ROCK LAYERS			
100	120	MED-COARSE SAND			
120	140	MEDIUM SAND			
140	160	MEDIUM SAND CLAY LAYERS			
160	210	FINE - MED SAND			
210	220	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/20/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 04/01/97 under the business name of JOE'S WELL SERVICE, INC.	by (signature) <i>Judie Clink</i>
--	-----------------------------------

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 SW 1/4	16	T 25 S	R 27 W

2 WATER WELL OWNER:	NIEMIER, FLORA MRS.	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	8 NATHAN ENGLISH	Application Number:
City, State, ZIP code :	CIMARRON, KS 67835-	

FROM	TO	LITHOLOGIC LOG
220	240	CLAY ROCK LAYERS BLUE SHALE