

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Gray

Location listed as:

Section-Township-Range: 21-25S-27EFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SW SW NW

Location changed to:

21-25S-27WSW SW NW

Other changes: Initial statements: _____

Changed to: _____

Comments: E changed to Wverification method: County maps, location and address informationinitials: MB date: 3-3-06submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SW 1/4 SW 1/4 NW 1/4	21	T 25 S	R 27 E

Distance and direction from nearest town or city street address of well if located within city?
FROM CIMARRON - 1 NORTH ON HIGHWAY 23, 2 1/2 E AND 2 NORTH

2 WATER WELL OWNER: VORAN, MRS. LESTER

RR#, St. Address, Box #: BOX 997

City, State, ZIP code : CIMARRON, KS 67835-

Board of Agriculture, Division of Water Resources

Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 275 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 131 ft. below land surface measured on mo/day/yr 10/07/05
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

E Bore Hole Diameter 10 in. to 275 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC

CASING JOINTS: CLAMPED

Blank casing diameter 5 in. to 275 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 210 ft. to 270 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 275 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: ABANDONED WELL

Direction from well? EAST

How many feet? 20

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY			
40	60	32 TAN CLAY 35 CALACHIE			
60	80	32 TAN CLAY 11 BROWN CLAY 35 CALACHIE			
80	100	35 CALACHIE 39 SAND ROCK 02 FINE SAND			
100	120	37 FIN-COAR SAN 06 SMALL GRAVEL			
120	140	37 FIN-COAR SAN 06 SMALL GRAVEL 05 CLAY			
140	160	05 CLAY 02 FINE SAND			
160	180	02 FINE SAND 05 CLAY 35 CALACHIE			
180	200	05 CLAY 35 CALACHIE 10 FINE-MEDSAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/12/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/07/05 under the business name of JOR'S WELL SERVICE, INC. by (signature) Judith Cick

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SW 1/4 SW 1/4 NW 1/4	21	T 25 S	R 27 E

2 WATER WELL OWNER: VORAN, MRS. LESTER

RE#, St. Address, Box #: BOX 997

City, State, ZIP code : CIMARRON, KS 67835-

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
200	220	37 FIN-COAR SAN 17 CLAY LAYERS
220	240	37 FIN-COAR SAN
240	255	37 FIN-COAR SAN 06 SMALL GRAVEL
255	260	05 CLAY
260	265	37 FIN-COAR SAN 06 SMALL GRAVEL
265	280	05 CLAY 07 BLUE SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 10/12/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/07/05 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justus Creek*