

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	NW 1/4 NW 1/4 SW 1/4	24	T 25 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?

FROM CIMARRON - 4 MILES NORTH ON HIGHWAY 23

2 WATER WELL OWNER: KOPPER, KENT

RR#, St. Address, Box #: Board of Agriculture, Division of Water Resources  
City, State, ZIP code : CIMARRON, KS 67835- Application Number: \_\_\_\_\_

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 140 ft. below land surface measured on mo/day/yr 02/15/11  
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 65 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 12 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASING CASING JOINTS: CERTA-LOC

Blank casing diameter 6 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 180 ft. to 260 ft., From 0 ft. to 0 ft.  
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 26 ft. to 265 ft., From 0 ft. to 0 ft.  
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 6 ft. to 26 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY 35 CALACHIE			
40	60	32 TAN CLAY 26 RED CLAY 35 CALACHIE			
60	80	05 CLAY 35 CALACHIE 02 FINE SAND			
80	100	05 CLAY 35 CALACHIE 37 FIN-COAR SAN			
100	120	37 FIN-COAR SAN 39 SAND ROCK			
120	140	37 FIN-COAR SAN			
140	180	10 FINE-MEDSAND 17 CLAY LAYERS			
180	200	37 FIN-COAR SAN			
200	220	37 FIN-COAR SAN 06 SMALL GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/02/11 under the business name of JOE'S WELL SERVICE, INC.

by (signature) *Judith Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	MW 1/4 NW 1/4 SW 1/4	24	T 25 S	R 27 W

2 WATER WELL OWNER: KOPPER, KENT

RR#, St. Address, Box # :

City, State, ZIP code : CINARRON, KS 67835-

Board of Agriculture, Division of Water Resources  
Application Number: \_\_\_\_\_

FROM	TO	LITHOLOGIC LOG
220	240	10 FINE-MEDSAND
240	265	10 FINE-MEDSAND 04 COARSE SAND 06 SMALL GRAVE
265	280	05 CLAY 08 ROCK LAYERS 07 BLUE SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/02/11, under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*