

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction SW 1/4 SW 1/4 NE 1/4	Section number 4	Township number T 25 S	Range number R 28 E
2. Distance and direction from nearest town or city: Cimarron, Kansas Street address of well location if in city:			3. Owner of well: Leonard Burkhardt R.R. or street: City, state, zip code: Cimarron, Kansas		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: SW corner of NE 1/4, Sec. 4, T25S, R28W, Gray County, Kansas.		
5. Type and color of material			From	To	6. Bore hole dia. 28 in. Completion date 22 Jan. 76 Well depth 251 ft.
g Top soil			0	2	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Tan clay			2	46	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Limestone			46	63	9. Casing: Material Stl Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 38 lbs./ft. Dia. 16 in. to 160 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Limestone & Fine sand			63	88	10. Screen: Manufacturer's name Doerr, Layne & Foster Louver, Millslot 16" Type <input type="checkbox"/> Dia. <input type="checkbox"/> Slot/gauze 1/8" Length 91' Set between 160 ft. and 251 ft. ft. and ft.
Fine to coarse sand with tan clay			88	100	Gravel pack? yes Size range of material 4.4mm
Fine to coarse sand medium gravel			100	119	11. Static water level: <input type="checkbox"/> mo./day/yr. 128 ft. below land surface Date 10-15-75
Coarse sand with tan and green clay			119	140	12. Pumping level below land surfaces: 224 ft. after 1 hrs. pumping 550 g.p.m. 229 ft. after 1 hrs. pumping 540 g.p.m. Estimated maximum yield 550 g.p.m.
Tan clay with sand streaks			140	161	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Fine to coarse sand, med. grvl, white streaks			161	170	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> <input type="checkbox"/> Inches above grade
Fine sand with tan clay			170	201	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
Tan clay with fine to coarse sand			201	217	16. Nearest source of possible contamination: Unk ft. Direction Type Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Fine to coarse sand medium gravel			217	251	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 10KH HP 80 Volts <input type="checkbox"/> Length of drop pipe 240 ft. capacity 450 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Yellow clay			251	256	
Black shale			256	260	
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 150 Business name License No. Address Garden City, Kansas Signed [Signature] Date 1/4 Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5