

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: GRAY SW 1/4 SW 1/4 SE 1/4 18 T 25 S R 28 N

Distance and direction from nearest town or city street address of well if located within city?
 FROM INGALLS ON BLACKTOP 3 NORTH & 3/4 MILES EAST

2 WATER WELL OWNER: WINTER RANCH
 RR#, St. Address, Box #: BOX 115 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 305 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 162 ft. below land surface measured on mo/day/yr 06/01/09
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 305 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 305 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 240 ft. to 300 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 305 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 35 CALACHIE			
20	40	35 CALACHIE 24 THINROCLAYER			
40	60	08 ROCK LAYERS 02 FINE SAND			
60	80	37 FIN-COAR SAM			
80	100	37 FIN-COAR SAM 06 SMALL GRAVEL			
100	120	37 FIN-COAR SAM 06 SMALL GRAVEL 05 CLAY			
120	140	37 FIN-COAR SAM 05 CLAY			
140	160	02 FINE SAND 05 CLAY 35 CALACHIE			
160	180	05 CLAY 35 CALACHIE			
180	200	02 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/12/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Quindrick*

(Continued)

WATER WELL RECORD Form WNC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: GRAY SW 1/4 SW 1/4 SE 1/4 18 T 25 S R 28 W

2 WATER WELL OWNER: WINTER RANCH
RR#, St. Address, Box #: BOX 115 Board of Agriculture, Division of Water Resources
City, State, ZIP code : DODGE CITY, KS 67801- Application Number:

FROM	TO	LITHOLOGIC LOG
200	240	10 FINE-MEDSAND
240	260	37 FIN-COAR SAN 06 SMALL GRAVEL
260	280	10 FINE-MEDSAND 17 CLAY LAYERS
280	300	37 FIN-COAR SAN 05 CLAY 08 ROCK LAYERS
300	320	08 ROCK LAYERS 07 BLUE SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/12/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justin Creek*