

WATER WELL RECORD Form #WC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 035 GRAY | SE 1/4 NE 1/4 NE 1/4 | 15 | T 25 S | R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 MILES NW & 1 1/2 MILES NORTH OF INGALLS

2 WATER WELL OWNER: IRSIK G & B FARMS, INC.
 RR#, St. Address, Box # : P.O. BOX 19, ROUTE 1 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : INGALLS, KS 67853- Application Number: 16,080

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 148 ft. below land surface measured on mo/day/yr 02/12/96
Pump test data: Well water was 246 ft. after 4 hours pumping 1285 gpm
Estimated Yield 1285 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 24 in. to 290 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 02 IRRIGATION
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 167 ft. to 287 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 290 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 200

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	52	04 SANDY CLAY 31 CALICHE 05 SAND			
52	100	05 SAND 13 FINE GRAVEL 01 CLAY			
100	114	07 FINE SAND 08 MEDIUM SAND			
114	120	01 CLAY			
120	142	05 SAND 28 ROCK			
142	180	05 SAND 13 FINE GRAVEL 28 ROCK			
180	189	05 SAND 11 GRAVEL 28 ROCK			
189	196	04 SANDY CLAY			
196	208	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/08/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/26/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

