

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
 COUNTY: 035 GRAY | SE 1/4 SE 1/4 SE 1/4 | 14 | T 25 S | R 29 W

Distance and direction from nearest town or city street address of well if located within city?  
 4 MILES NORTH AND 2 MILES WEST OF INGALLS KS.

2 WATER WELL OWNER: IRSIK G&B FARMS INC  
 RR#, St. Address, Box #: P.O. BOX 19, RT.1 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: INGALLS, KS, KS 67853-0019 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 301 | ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 150 ft. below land surface measured on mo/day/yr 09/20/96  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 25 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 11 in. to 301 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 6 in. to 301 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 201 ft. to 301 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 194 ft., From 0 ft. to 0 ft.  
 From 204 ft. to 301 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 194 ft. to 204 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 09 FEEDYARD  
 Direction from well? WEST How many feet? 200

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	40	01 CLAY 31 CALICHE			
40	52	04 SANDY CLAY			
52	56	31 CALICHE 04 SANDY CLAY			
56	63	07 FINE SAND 09 COARSE SAND 31 CALICHE			
63	70	04 SANDY CLAY			
70	79	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			
79	145	07 FINE SAND 09 COARSE SAND 12 V. FINE GRAV			
145	152	04 SANDY CLAY 05 SAND			
152	182	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/25/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/28/96 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Jim Fullen*

