

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 035 GRAY | NE 1/4 NE 1/4 SE 1/4 | 15 | T 25 S | R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 MILES NORTH AND 1 1/2 MILES WEST OF INGALLS

2 WATER WELL OWNER: CLARENCE IRSIK
 RR#, St. Address, Box #: RT. 1, BOX 19 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: INGALLS, KS 67853- Application Number: 16,080

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 142 ft. below land surface measured on mo/day/yr 04/23/93
 Pump test data: Well water was 235 ft. after 4 hours pumping 830 gpm
 Estimated Yield 750 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 290 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: ~~DEWATERING~~ IRRIGATION 62
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 220 ft. to 280 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 290 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 120

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	43	01 CLAY 31 CALICHE			
43	57	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			
57	113	17 SAND & GRAVL			
113	122	04 SANDY CLAY 07 FINE SAND			
122	146	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
146	177	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			
177	190	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
190	215	01 CLAY 07 FINE SAND			
215	280	08 MEDIUM SAND 09 COARSE SAND 14 MED GRAVEL			

DRILLER'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
 Driller's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/26/93
 Name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NE 1/4 NE 1/4 SE 1/4	15	T 25 S	R 29 W

2 WATER WELL OWNER:	CLARENCE IRSIK	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT. 1, BOX 19	Application Number: 16,080
City, State, ZIP code :	INGALLS, KS 67853-	

FROM	TO	LITHOLOGIC LOG
280	282	01 CLAY
282	289	36 GYP ROCK
289	292	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/26/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Lichenath