

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SW 1/4 SE 1/4 SE 1/4 20 T 25 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2.25 MILES EAST AND 0.5 MILES SOUTH OF CHARLESTON.

2 WATER WELL OWNER: KANSAS DEPT. OF TRANS.
 RR#, St. Address, Box #: RT. Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 116 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 33 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 33 ft. below land surface measured on mo/day/yr 06/23/92
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10.62 in. to 116 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 6 in. to 116 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 96 ft. to 116 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 55 ft., From 0 ft. to 0 ft.
 From 65 ft. to 116 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 55 ft. to 65 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	01 CLAY			
3	50	05 SAND 14 MED GRAVEL 01 CLAY			
50	71	01 CLAY			
71	100	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
100	116	05 SAND			
116	120	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/24/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/25/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*