

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY NW 1/4 NW 1/4 NE 1/4 27 T 25 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 3 MILES WEST 2 MILES NORTH OF INGALLS

2 WATER WELL OWNER: INGALLS FEED YARD
 RR#, St. Address, Box #: RUAL ROUTE 2 BOX 2
 City, State, ZIP code : INGALLS, KS 67853- Board of Agriculture, Division of Water Resources
 Application Number: 16079

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 294 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 X WELL'S STATIC WATER LEVEL 142 ft. below land surface measured on mo/day/yr 05/03/94
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 NW NE Estimated Yield 100 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 W E Bore Hole Diameter 17.5 in. to 294 ft., and in. to 0 ft.
 e WELL WATER TO BE USED AS: 03 FEEDLOT
 SW SE Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes
 / /

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 8 in. to 294 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 214 ft. to 234 ft., From 0 ft. to 0 ft.
 From 254 ft. to 294 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 170 ft., From 0 ft. to 0 ft.
 From 180 ft. to 294 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 170 ft. to 180 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 09 FEEDYARD
 Direction from well? SOUTH EAST How many feet? 500

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	61	01 CLAY 36 GYP ROCK			
61	71	01 CLAY 05 SAND			
71	85	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL			
85	100	01 CLAY 05 SAND			
100	107	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
107	125	04 SANDY CLAY			
125	135	07 FINE SAND 08 MEDIUM SAND			
135	139	01 CLAY			
139	152	17 SAND & GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/03/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bob Knight*


(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	1 Fraction	1 Section Number	1 Township Number	1 Range Number
COUNTY: 035 GRAY	1 NW 1/4 NW 1/4 NE 1/4	1 27	1 T 25 S	1 R 29 W

2 WATER WELL OWNER:	INGALLS FEED YARD	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RUAL ROUTE 2 BOX 2	Application Number: 16079
City, State, ZIP code :	INGALLS, KS 67853-	

FROM	TO	LITHOLOGIC LOG
152	158	01 CLAY
158	162	07 FINE SAND
162	182	01 CLAY 28 ROCK
182	198	07 FINE SAND 08 MEDIUM SAND 01 CLAY
198	200	01 CLAY
200	203	07 FINE SAND
203	205	01 CLAY
205	218	07 FINE SAND 08 MEDIUM SAND 01 CLAY
218	220	01 CLAY
220	233	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
233	246	05 SAND 01 CLAY
246	250	01 CLAY
250	276	05 SAND 13 FINE GRAVEL 01 CLAY
276	282	01 CLAY 05 SAND
282	294	09 COARSE SAND 11 GRAVEL 28 ROCK
294	297	01 CLAY
297	305	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/03/94 and this record is true to the best of my knowledge and belief, Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)	
---	---