

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction NE 1/4 SE 1/4 SE 1/4	Section number 28	Township number T 25 S R 29 E/W	Range number 29
2. Distance and direction from nearest town or city: 3 mi West, 1 North of Ingalls, Kansas Street address of well location if in city:			3. Owner of well: Norbert Irsik R.R. or street: City, state, zip code: Ingalls, Kansas 67853		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Sketch map:			6. Bore hole dia. 10 7/8 . Completion date 8/22/77 Well depth 190 ft.		
5. Type and color of material See Attachement			7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material Plastic Above or below Glued Throated ☐ Welded ☐ Surface 12 in. RMP 65/8 Weight 440 lbs./ft. Dia. 65/8 in. to 190 ft. depth Wall Thickness: inches or Dia. 65/8 in. to 190 ft. depth gage No. 316		
			10. Screen: Manufacturer's name Jet Stream Type PVC Dia. 6 5/8 Slot gage .040 Length 50 Set between 120 ft. and 150 ft. 165'-175' ft. and 180'-190' ft. Gravel pack? Yes Size range of material 8-12 round		
			11. Static water level: 42 ft. below land surface Date 8/23/77 mo./day/yr.		
			12. Pumping level below land surfaces: Not pumped ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.		
			13. Water sample submitted: ____ mo./day/yr. Yes ☒ No ☐ Date ____		
			14. Well head completion: 12 inches above grade ☒ Pitless adapter		
			15. Well cased? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: ft. 150 Direction NW Type Ceptic tank Well disinfected upon completion? ☒ Yes ☐ No		
17. Pump: Not installed Manufacturer's name Red Jacket Model number N14cc HP 2 Volts 230 Length of drop pipe 168 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Henkle Drilling & Sply 145 Business name License No. Address Box 639, Garden City, KS Signed Bruce J. Richmond Date 8/23/77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

DRILLERS TEST LOG

CUSTOMERS NAME Norbert Irsik DATE 8/19/77
 STREET ADDRESS _____ TEST # 2 E. LOG Yes
 CITY & STATE Ingalls, Kansas DRILLER Rector
 COUNTY Gray QUARTER SE SECTION 28 TOWNSHIP 25 RANGE 29
 LOCATION 1000' North of the SE corner of the 1/4 and 300' West.

				DOMESTIC WELL LOCATION	
				Static Water Level _____	
				Proposed Well Depth _____	
%	FOOTAGE			DESCRIPTION OF STRATA	
	From	Pay	To		
	0		5	Surface soil	
	5		20	Brown sandy clay. some sand.	
	20		37	Sand fine to med coarse. small gravel.	
	37		41	Brown sandy clay.	
	41		50	Sand fine to med coarse. small gravel. Loose - used alot of water.	
	50		80	Brown clay and caliche.	
	80		95	Brown sandy clay. some sand.	
55	95	23	113	Sand fine to med coarse. med to small gravel. Loose - use water.	
20	113	7	120	Sand med coarse and brown sandy clay.	
70	120	31	151	Sand fine to med coarse. small to med gravel with a few med size gravel rock. Loose - used alot of water.	
	151		165	Brown clay - drilled firm.	
40	165	5	170	Sand fine to med coarse - loose. Used water.	
	170		184	Brown clay.	
50	184	3	187	White and tan rock. med coarse gravel. some sand. Used alot of water.	
	187		191	Yellow clay and soapstone.	
	191		200	Blue shale - very hard.	
		69			
TOTAL DEPTH OF WELL 190'					
Casing Schedule: 190' - 180' - Perf.					
180' - 175' - Plain					
175' - 165' - Perf.					
165' - 150' - Plain					
150' - 120' - Perf.					
120' - 0 - Plain					
1000 lbs fountain gravel pack.					

GARDEN CITY, KS
 Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS