

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Gray	Fraction SE 1/4 SW 1/4 NE 1/4	Section number 28	Township number T 25 S	Range number R 29 E
2. Distance and direction from nearest town or city: 2 miles West of Ingalls Street address of well location if in city:				3. Owner of well: Norbert Irsik R.R. or street: City, state, zip code: Ingalls, Kansas 67853		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: Drilled Well 12/5/76		6. Bore hole dia. 26 in. Completion date 2-7-76 Well depth 184 ft.		
5. Type and color of material See Attachment		From		To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
						8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
						9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 31 lbs./ft. Dia. 16 in. to 184 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 188
						10. Screen: Manufacturer's name Brown Type Louvered Dia. 16" Slot/gauze 1/8" Length 30' Set between 150 ft. and 180 ft. ft. and ft. Gravel pack? yes Size range of material 1/4 - 1/8
						11. Static water level: 39 ft. below land surface Date 2/7/76
						12. Pumping level below land surface: 140 ft. after ☐ hrs. pumping 842 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
						13. Water sample submitted: ☐ Yes ☒ No Date
						14. Well head completion: ☐ Pitless adapter 12 inches above grade
						15. Well grouted? Yes With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: None ft. Direction Type Observed Well disinfected upon completion? ☐ Yes ☒ No
				17. Pump: ☒ X Not installed Manufacturer's name Model number ☐ HP ☐ Volts Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Henkle Drilling & Supply 145 Business name License No. Address Box 639, Garden City, Kansas Signed J. W. Henkle Date 3-3-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3

DRILLERS TEST LOG

CUSTOMERS NAME Norbert Irsik DATE 1-15-76
STREET ADDRESS _____ TEST # 6 E-Log 190'
CITY & STATE Ingalls, Kansas DRILLER Rector
COUNTY Gray QUARTER NE SECTION 28 TOWNSHIP 25 RANGE 29

LOCATION 660' W of Test #5

[illegible]

GARDEN CITY, KANSAS
PHONE 276-3276

HENKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUBLETTE, KANSAS
PHONE 675-4311

WELL HOLES*****STOCK WELLS*****IRRIGATION AND INDUSTRIAL WELLS*****