

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 NW 1/4	Section number 5	Township number T 25 S R 3W E/W	Range number
2. Distance and direction from nearest town or city: Street address of well location if in city: 2 1/2 North, 1 West of Mt. Hope, Kansas				3. Owner of well: Ronnie Young R.R. or street: Mt. Hope, Kansas City, state, zip code:		
4. Locate with "X" in section below: Sketch map:				6. Bore hole dia. 12 in. Completion date 12-27-77 Well depth 80 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material PVC Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 3.96 lbs./ft. Dia. 6 in. to 80 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .316		
5. Type and color of material				From	To	10. Screen: Manufacturer's name PVC NSF approved 200 PSI Type PVC 200 PSI Dia. 6" Slot/gauge .100 Length 20' Set between 60 ft. and 80 ft. Gravel pack? yes Size range of material 1/4-1/8"
Topsoil				0	2	11. Static water level: 12 ft. below land surface Date 12-27-77
Sand and Gravel				2	22	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
Clay				22	42	13. Water sample submitted: ____ mo./day/yr. Yes ☐ No ☐ Date
Sand (Medium)				42	52	14. Well head completion: 12 capped ____ Pitless adapter ____ inches above grade
Clay				52	60	15. Well grouted? yes 1-2 fine sand mix With: ____ Neat cement ____ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
Sand (Medium)				60	80	16. Nearest source of possible contamination: NONE ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☒ Not installed Manufacturer's name ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: ____ Submersible ____ Turbine ____ Jet ____ Reciprocating ____ Centrifugal ____ Other
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. ____ Address ____ Signed M. Arnold Date 12-31-77 Authorized representative
18. Elevation: Topography: ____ Hill ____ Slope ____ Upland ____ Valley		19. Remarks: Flat Ground No apparent source for contamination.				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5