


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Sedgwick</u>		SW 1/4 NE 1/4 NW 1/4	19	T 25 S	R 3
Distance and direction from nearest town or city street address of well if located within city? 2 miles West of Mt. Hope, KS					
2 WATER WELL OWNER: Warren Miller					
RR#, St. Address, Box # : RR 1, Box 78					
City, State, ZIP Code : Mt. Hope, KS 67108					
Board of Agriculture, Division of Water Resources Application Number: Permit #38987					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 95 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ... 36 ... ft. below land surface measured on mo/day/yr 1-21-89			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 800-900 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter ... 30 ... in. to ... 95 ... ft., and ... in. to ... ft.			
WELL WATER TO BE USED AS:					
5 Public water supply 8 Air conditioning 11 Injection well					
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)					
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well					
Was a chemical/bacteriological sample submitted to Department? Yes.....No...X.....; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes X No					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped					
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded					
7 Fiberglass Threaded					
Blank casing diameter 16 in. to 55 ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface 12 in., weight 25.6 lbs./ft. Wall thickness or gauge No. 616					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)					
12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
7 Torch cut 10 Other (specify) 070 slot					
SCREEN-PERFORATED INTERVALS: From 55 ft. to 95 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 20 ft. to 95 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage					
Direction from well? None within 1/4 mile How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	Top Soil			
3	7	Clay--Buff			
7	45	Clay, Red Hard			
45	56	Clay, Red Soft			
56	61	Sand, fine Tight			
61	74	Sand, Coarse, Tight			
74	94	Sand, Coarse, Loose			
94	95	Shale--Green			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1-21-89 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 1-23-89					
under the business name of <u>Peterson Irrigation, Inc.</u> by (signature) <u>Mike Peterson</u>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.					