

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SW 1/4 NE 1/4	Section number 29	Township number 25	Range number 3W
2. Distance and direction from nearest town or city: Street address of well location if in city:		Well #3 1 South of Mt. Hope, Kansas		3. Owner of well: R.R. or street: City, state, zip code: Albert Gruenbacher R. R. #1 Colwich, Kansas		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>30</u> in. Completion date <u>5-4-77</u> Well depth <u>200</u> ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Topsoil		0	2	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Sandy Clay		2	15	9. Casing: Material <u>Transite</u> Height: Above or below <u>16</u> See #19 Threading <u>Welded</u> Surface <u>12</u> in. RMP <u>PVC</u> Weight <u>37</u> lbs./ft. Dia. <u>16</u> in. to <u>200</u> ft. depth Wall Thickness: <u>inches</u> Dia. <u>in.</u> to <u>ft.</u> depth gage No. <u>374</u>		
Sand and Gravel		15	43	10. Screen: Manufacturer's name <u>Johnson</u> Type <u>irrigator</u> Dia. <u>16"</u> Slot/groove <u>100</u> Length <u>20'</u> Set between <u>180</u> ft. and <u>200</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4-1/8"</u>		
Blue Clay (Soft)		43	102	11. Static water level: <u>25</u> ft. below land surface Date <u>5-4-77</u>		
Fine sand		102	105	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.		
Blue Clay		105	114	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☐ No Date ____		
Fine Sand		114	120	14. Well head completion: <u>12</u> inches above grade ☐ Pitless adapter		
Sand and Gravel		120	136	15. Well grouted? <u>yes 1-2 fine sand</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
Blue Clay		136	145	16. Nearest source of possible contamination: <u>NONE</u> ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No		
Sand and Gravel		145	165	17. Pump: ☐ Not installed Manufacturer's name <u>Valley</u> Model number <u>12-HMO-04</u> Volts <u>460</u> Length of drop pipe <u>140</u> ft. capacity <u>800</u> g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Gravel		165	200	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Harp Well & Pump</u> 236 Business name <u>Wichita, Kansas</u> License No. ____ Address ____ Signed <u>M. Arnold</u> Date <u>11-22-77</u> Authorized representative		
18. Elevation:		19. Remarks: Flat Ground From #9 Banded But Joint No apparent source for contamination.				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5