


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>SEDGWICK</u> Renov	Fraction <u>SW 1/4 NW 1/4 NE 1/4</u>	Section number <u>30</u>	Township number <u>T 25 S</u>	Range number <u>R 3 E</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1 S, 1 1/4 W Mt. Hope</u>			3. Owner of well: <u>Steve Beal</u> R.R. or street: <u>Mt. Hope, Kansas 67108</u> City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>3/15/77</u> Well depth <u>71</u> ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Topsoil</u>		<u>0</u>	<u>1</u>	9. Casing: Material <u>C-Asb.</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u> </u> lbs./ft. Dia. <u>16</u> in. to <u>58</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>3/4</u>		
<u>Fine Sand</u>		<u>1</u>	<u>20</u>	10. Screen: Manufacturer's name <u>Peerless Johnson</u> Type <u>Cemt-Asb.</u> Dia. <u>16"</u> Slot/gauze <u>44</u> Length <u>13'</u> Set between <u>58</u> ft. and <u>71</u> ft. <u> </u> ft. and <u> </u> ft.		
<u>Clay & Sand</u>		<u>20</u>	<u>40</u>	Gravel pack? ☒ Size range of material <u>3/8</u>		
<u>Med. Gravel</u>		<u>40</u>	<u>70</u>	11. Static water level: <u>39</u> ft. below land surface Date <u> </u> mo./day/yr.		
				12. Pumping level below land surfaces: <u>45</u> ft. after <u>1</u> hrs. pumping <u>800</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>900</u> g.p.m.		
				13. Water sample submitted: <u> </u> mo./day/yr. Yes ☐ No ☒ Date <u> </u>		
				14. Well head completion: <u> </u> Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? ☒ With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: ft. <u>300</u> Direction <u>W</u> Type <u>Irr. well</u> Well disinfected upon completion? Yes ☐ No ☒		
				17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless</u> Model number <u>7138</u> HP <u>60</u> Volts <u> </u> Length of drop pipe <u>65</u> ft. capacity <u>900</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irrigation 238</u> Business name <u>Maize</u> License No. <u> </u> Address <u> </u> Signed <u>X Weninger</u> Date <u>4/4/77</u> Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5