

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 NW 1/4 NW 1/4	Section number 36	Township number T 25 S	Range number R 3 E (W)
2. Distance and direction from nearest town or city: Street address of well location if in city: 25. 3 E, Mt. Hope			3. Owner of well: Joe Rupie R.R. or street: Mr. Hope, Ks. 67108 City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 8/30/79 Well depth 97 ft.	
		open field		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
5. Type and color of material		From To		9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 97 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gage No. 314	
				10. Screen: Manufacturer's name Johnson Type Cm-Asb Dia. 16" Slot/gauze 1/4" Length 39' Set between 58 ft. and 97 ft. ft. and ☐ ft. Gravel pack? ☒ Size range of material 3/8	
Topsoil		0 1		11. Static water level: 24 ft. below land surface Date 8/29/79	
Fine Sand		1 10		12. Pumping level below land surfaces: 35 ft. after 1 hrs. pumping 600 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1200 g.p.m.	
Clay-gray		10 16		13. Water sample submitted: ☐ Yes ☒ No Date ☐	
Fine Sand		16 22		14. Well head completion: 12 inches above grade ☐ Pitless adapter	
Clay		22 30		15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
Med. Sand		30 45		16. Nearest source of possible contamination: none ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No	
Clay		45 54		17. Pump: ☐ Not installed Manufacturer's name Peerless Model number 9569 HP 40 Volts ☐ Length of drop pipe 70' ft. capacity 950 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Good Gravel		54 97		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize License No. ☐ Address A. Weninger Signed A. Weninger Date 4/7/80 Authorized representative	
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:				
Topography: ☐ Hill ☒ Slope ☒ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5