

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SW 1/4 SE 1/4	Section number 36	Township number T 25 S R	Range number 3W E/W
2. Distance and direction from nearest town or city: 2 n, 1 1/2 E, of Andale, Kansas			3. Owner of well: albert Gruenbacher			
Street address of well location if in city: Well # 1			R.R. or street: R. R. #1			
			City, state, zip code: Colwich, Kansas			
4. Locate with "X" in section below:			Sketch map:			
5. Type and color of material			From	To	6. Bore hole dia. 30 in. Completion date 5-2-77	
					Well depth 95 ft.	
Topsoil			0	2	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Red Clay			2	40	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand and Gravel			40	55	9. Casings: Material Transite Height: Above or below SEE # 19	
Coarse Sand and Gravel			55	63	Threaded ☐ Welded ☐ Surface 12 in.	
Grey Clay			63	68	RMP ☐ PVC ☐ Weight 37 lbs./ft.	
Fine Sand and Gravel			68	83	Dia. 16 in. to 95 ft. depth Wall Thickness: inches or 3/4	
Brown Clay			83	85	Dia. ☐ in. to ☐ ft. depth Page No. ☐	
Fine Sand and Gravel			85	93	10. Screen: Manufacturer's name Johnson	
Green Clay			93	95	Type irrigator Dia. 16"	
					Slot/size .100 Length 20'	
					Set between 52 ft. and 62 ft.	
					Gravel pack yes Size range of material 1/2-1/8"	
					11. Static water level: 35 ft. below land surface Date 5-2-77	
					12. Pumping level below land surfaces: 12 inches above grade	
					13. Water sample submitted: yes 1-2 fine sand mi	
					With: ☐ Neat cement ☐ Bentonite ☒ Concrete	
					Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: NONE	
					ft. ☐ Direction ☐ Type ☐	
					Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: Valley Not installed	
					Manufacturer's name 12-HMO-04 HP 75 Volts 460	
					Model number 80 ft. capacity 950 g.p.m.	
					Length of drop pipe 80 ft. capacity 950 g.p.m.	
					Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks: Flat Ground			
Topography: From # 9 - Banded But Joint						
☐ Hill ☐ Slope ☐ Upland ☐ Valley			No apparent source for contamination.			
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.			
			Harp Well & Pump 236			
			Business name Wichita, Kansas License No.			
			Address M. Arnold Date 11-22-77			
			Signed M. Arnold Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

MI-1023