

1 LOCATION OF WATER WELL:	Fraction COUNTY: GRAY SB 1/4 SB 1/4 NW 1/4	Section Number 24	Township Number T 25 S	Range Number R 30 W
---------------------------	--	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
CHARLESTON, KS

2 WATER WELL OWNER: RENICK & REYNOLDS
RR#, St. Address, Box #: BOX 12 -- R.R. #2
City, State, ZIP code : INGALLS, KS 67853-
Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

W	NW	NE	
X			
SW		SE	

4 DEPTH OF COMPLETED WELL 200 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 65 ft. below land surface measured on mo/day/yr 04/21/95
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

5 Bore Hole Diameter 9 in. to 200 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

6 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From 175 ft. to 195 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 40 ft. to 200 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

7 GROUT MATERIAL BENTONITE
Grout Intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: ABANDONED WELL
Direction from well? WEST How many feet? 15

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	15	SANDY CLAY GRAVEL			
15	40	CLAY SANDY CLAY			
40	55	SAND GRAVEL			
55	80	YELLOW CLAY			
80	110	CLAY SANDY CLAY			
110	140	FINE - MED SAND GRAVEL			
140	188	YELLOW CLAY			
188	194	FINE - MED SAND GRAVEL			
194	200	YELLOW CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/22/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/06/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) Judith Crust