

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 | COUNTY: 095 GRAY | W/C 1/4 LOT 5 1/4 NW 1/4 | 27 | T 25 S | R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 MILE SOUTH AND 2 MILES WEST OF CHARLESTON

2 WATER WELL OWNER: MARTIAN RANCH INC.

RR#1, St. Address, Box #: R.R. 2, BOX 17
 City, State, ZIP code : INGALLS, KS 67053-

Board of Agriculture, Division of Water Resources
 Application Number: 12,031

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
 | Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 |
 | | | | | WELL'S STATIC WATER LEVEL 24 ft. below land surface measured on mo/day/yr 05/03/03
 | | | | | Pump testdata: Well water was 81 ft. after 4 hours pumping 578 gpm
 | | | | |
 | | | | | X Estimated Yield 600 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 | | | | |
 | | | | | V E Bore Hole Diameter 21 in. to 165 ft., and in. to 0 ft.
 | | | | |
 | | | | | e WELL WATER TO BE USED AS: 02 IRRIGATION
 | | | | |
 | | | | | SW SE Was a chemical/bacteriological sample submitted to department? No ;
 | | | | |
 | | | | | If yes, mo/day/yr sample was submitted Water well disinfected? No
 | | | | |
 | | | | |

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: WELDED

Blank casing diameter 12 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 12 lbs/ft. Wall thickness or gauge No. .42

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 05 ft. to 05 ft., From 115 ft. to 125 ft.

From 95 ft. to 105 ft., From 135 ft. to 146 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 35 ft., From 0 ft. to 0 ft.

From 45 ft. to 165 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout intervals: From 0 ft. to 20 ft., From 35 ft. to 45 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? EAST

How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	37	00 COARSE SAND 14 MED GRAVEL 18 V CRS GRAVEL			
37	41	04 SANDY CLAY 20 LIMESTONE			
41	72	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
72	80	01 CLAY			
80	89	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
89	93	01 CLAY			
93	105	08 MEDIUM SAND 09 COARSE SAND 14 MED GRAVEL			
105	116	04 SANDY CLAY			
116	125	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/07/03 under the business name of MENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
1 COUNTY: 035 GRAY N/C 1/4 LOT 5 1/4 NW 1/4 27 T 25 S R 30 W

2 WATER WELL OWNER: MARTIN RANCH INC.

RR# 1, St. Address, Box # : R.R. 2, BOX 17

City, State, ZIP code : INGALLS, KS 67053-

Board of Agriculture, Division of Water Resources

Application Number: 12,931

3 SCREEN PERFORATED INTERVALS: From 155 ft. to 165 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

4 FROM : TO : LITHOLOGIC LOG

125	132	01 CLAY
132	144	07 FINE SAND 08 MEDIUM SAND
144	155	01 CLAY
155	163	08 MEDIUM SAND 09 COARSE SAND 14 MED GRAVEL
163	164	36 GYP ROCK
164	170	19 SHALE

5 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/07/93 under the business name of NEWKLE DRILLING & SUPPLY by (signature) *Bruce J. Lickens*