


USE PENCIL OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County GRAY	Fraction NW 1/4 SE 1/4 NW 4	Section number 35	Township number T 5 S R 30	Range number 17W
2. Distance and direction from nearest town or city: 1 3/4 south of Charleston 1 1/2 west Street address of well location if in city:				3. Owner of well: Don Renick (#57) R.R. or street: City, state, zip code: Ingalls, Ks. 67853		
4. Locate with "X" in section below: 				Sketch map:		
5. Type and color of material				6. Bore hole dia. 26 in. Completion date 4-20-76 Well depth 231 ft.		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 6.87 lbs./ft. Dia. 16 in. to 232 ft. depth Well thickness: inches or Dia. ☐ in. to ☐ ft. depth page No. ☐		
				10. Screen: Manufacturer's name Johnson Division Type Galv. Dia. 16" Slot/gauze 100 Length 20' Set between 121-131 ft. and 181-187 ft. Perf. 76-212 ft. and 131-171, 181-231 ft. Gravel pack? ☒ Size range of material 1/2" Down		
				11. Static water level: ☐ mo./day/yr. 30 ft. below land surface Date 3-15-76		
				12. Pumping level below land surfaces: 89 ft. after 3 hrs. pumping 1300 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1300 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No ☐ Date ☐		
				14. Well head completion: ☐ Pitless adapter 12 inches above grade		
				15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
16. Nearest source of possible contamination: N/A ft. ☐ Direction ☐ Type ☒ Well disinfected upon completion? ☐ Yes ☐ No						
17. Pump: Not installed Manufacturer's name Goulds US Pumps Model number 12 JHM HP 75 Volts ☐ Length of drop pipe 160 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other						
18. Elevation:		19. Remarks: Drilling done by Central Well & Pump Pratt, Ks.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter Wilson Drilling 208 Business address: Box A Garden city, Ks. Address: Box A Garden city, Ks. Authorized representative: [Signature] Date 8-12-76		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The
Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

DON RENICK
GRAY COUNTY
1-21-76

Location NW 35-25-30
½ Mile West From Pivot 56, Pivot 57
30 Feet West Of Pivot

Static Water Level - 50'

Test #3

0	3	Top Soil
3	8	Brown Sandy Clay
8	55	Med. Coarse Gravel (Loose)
55	73	Brown Sandy Clay
73	81	Fine To Med. Sandy Gravel (Loose)
81	89	Brown Sandy Clay
89	109	Fine To Med. Sand & Gravel (Loose)
109	114	Brown Sandy Clay
114	124	Fine To Med. Sand & Gravel
124	131	Brown Sandy Clay
131	142	Fine To Med. Sand & Gravel (Loose)
142	149	Brown Sandy Clay
149	158	Fine To Med Sand & Gravel
158	173	Brown Clay Stick
173	183	Brown Sandy Clay
183	199	Fine To Med. Sand & Gravel, Little Clay
199	216	Brown Sandy Clay
216	220	Fine To Med. Sand & Gravel
220	226	Brown Sandy Clay
226	231	Brown Sandy Clay, 2 Ft. Gravel, Rock Streak (Loose)
231	235	Shale

TD 231
Screen ?