

0B54

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 PINNEY NC $\frac{1}{2}$ NW $\frac{1}{4}$ NW 1/4 20 T 25 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HOLCOMB; APPX 7 1/2 MILES SOUTH & 1 MILE EAST

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
 RR#, St. Address, Box #: PO BOX 430 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HOLCOMB, 67 67851-0430 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	W	SW	SE
M			
i			
l			
e			

4 DEPTH OF COMPLETED WELL 460 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 211 ft. below land surface measured on mo/day/yr 5-17-05
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 7/8 in. to 460 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 4 in. to 460 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .337
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 380 ft. to 460 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 140 ft., From 0 ft. to 0 ft.
 From 160 ft. to 460 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 140 ft. to 160 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	30	04 SANDY CLAY			
30	63	05 SAND 11 GRAVEL			
63	70	04 SANDY CLAY			
70	87	05 SAND 13 FINE GRAVEL			
87	95	04 SANDY CLAY			
95	114	05 SAND			
114	138	01 CLAY			
138	148	07 FINE SAND 08 MEDIUM SAND			
148	202	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/25/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction 1/4 1/4 NW 1/4	Section Number 20	Township Number T 25 S	Range Number R 33 W
---	----------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
RR#, St. Address, Box # : PO BOX 430
City, State, ZIP code : HOLCOMB, 67 67851-0430

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
202	221	05 SAND
221	227	01 CLAY
227	245	05 SAND 13 FINE GRAVEL
245	274	04 SANDY CLAY 05 SAND
274	283	05 SAND 13 FINE GRAVEL
283	296	04 SANDY CLAY 05 SAND
296	319	05 SAND 13 FINE GRAVEL
319	342	04 SANDY CLAY 05 SAND
342	365	07 FINE SAND 08 MEDIUM SAND
365	368	04 SANDY CLAY
368	378	05 SAND
378	392	05 SAND 13 FINE GRAVEL
392	427	04 SANDY CLAY 05 SAND
427	437	07 FINE SAND 08 MEDIUM SAND
437	460	05 SAND
460	465	31 CALICHE 23 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/25/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruno J. Richman