

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 FINNEY SE 1/4 SW 1/4 NW 1/4 17 T 25 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HOLCOMB; 6 1/2 MILES SOUTH

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
 RR#, St. Address, Box #: PO BOX 430 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HOLCOMB, KS 67851-0430 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	W	X	---	---	E
i	---	---	---	---	---
l	---	SW	---	SE	---
e	---	---	---	---	---

4 DEPTH OF COMPLETED WELL 460 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 219 ft. below land surface measured on mo/day/yr 5/7-05
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 7/8 in. to 460 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 4 in. to 460 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .337
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 380 ft. to 460 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 170 ft., From 0 ft. to 0 ft.
 From 175 ft. to 460 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 170 ft. to 175 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	37	04 SANDY CLAY			
37	62	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
62	70	04 SANDY CLAY			
70	75	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
75	84	01 CLAY			
84	170	05 SAND 13 FINE GRAVEL 01 CLAY			
170	177	04 SANDY CLAY			
177	227	05 SAND 13 FINE GRAVEL 01 CLAY			
227	236	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/29/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	1/4 1/4 NW 1/4	17	T 25 S	R 33 W

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
RR#, St. Address, Box # : PO BOX 430
City, State, ZIP code : HOLCOMB, KS 67851-0430

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
236	264	05 SAND 13 FINE GRAVEL
264	289	04 SANDY CLAY 05 SAND
289	303	05 SAND 13 FINE GRAVEL
303	305	04 SANDY CLAY
305	328	05 SAND 01 CLAY
328	344	04 SANDY CLAY 05 SAND
344	430	05 SAND 13 FINE GRAVEL 01 CLAY
430	455	05 SAND 13 FINE GRAVEL
455	460	31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/29/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichman