

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 FINNEY : NC NW 1/4 34 T 25 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM GARDEN CITY; APPX 8 3/4 MILES SOUTH & 2 MILES WEST

2 WATER WELL OWNER: TRIANGLE H GRAIN & CATTLE
 RR#, St. Address, Box # : 1955 W. PLYMELL ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code : GARDEN CITY, KS 67846-8833 Application Number: 19,365

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

/ \				
1		X		NE
M				
i	W			E
l				
e		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 420 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 213 ft. below land surface measured on mo/day/yr 05/12/05
 Pump test data: Well water was 287 ft. after 4 hours pumping 1100 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 420 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 420 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .216
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 281 ft. to 321 ft., From 385 ft. to 415 ft.
 From 342 ft. to 362 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 420 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHWEST How many feet? 63

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	5	04 SANDY CLAY			
5	22	07 FINE SAND			
22	128	05 SAND 11 GRAVEL			
128	180	01 CLAY 05 SAND			
180	189	07 FINE SAND 08 MEDIUM SAND			
189	210	01 CLAY 05 SAND			
210	215	07 FINE SAND			
215	222	01 CLAY 05 SAND			
222	248	01 CLAY 20 LIMESTONE 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/10/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	1/4 NC 1/4 NW 1/4	34	T 25 S	R 33 W

2 WATER WELL OWNER: TRIANGLE H GRAIN & CATTLE
RR#, St. Address, Box # : 1955 W. PLYMELL ROAD
City, State, ZIP code : GARDEN CITY, KS 67846-8833

Board of Agriculture, Division of Water Resources
Application Number: 19,365

FROM	TO	LITHOLOGIC LOG
248	277	01 CLAY 20 LIMESTONE 11 GRAVEL
277	298	05 SAND 13 FINE GRAVEL
298	303	01 CLAY
303	312	07 FINE SAND 08 MEDIUM SAND
312	321	05 SAND 01 CLAY
321	340	01 CLAY 20 LIMESTONE 05 SAND
340	363	07 FINE SAND 08 MEDIUM SAND 01 CLAY
363	382	01 CLAY
382	401	23 SANDSTONE 31 CALICHE
401	415	31 CALICHE 23 SANDSTONE
415	431	31 CALICHE 20 LIMESTONE
431	460	31 CALICHE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/10/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Richman