

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 SW 1/4 NE 1/4	Section Number 18	Township Number T 25 S	Range Number R 33 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 6 1/2 MILES SOUTH

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT
RR#, St. Address, Box #: PO BOX 1078
City, State, ZIP code: GARDEN CITY, KS 67846-1078
Board of Agriculture, Division of Water Resources
Application Number: 39984

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	---	NW	---	NE
			X	
M	W	---	---	E
i				
l				
e				
		SW	---	SE
\				/

4 DEPTH OF COMPLETED WELL 432 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 189 ft. below land surface measured on mo/day/yr 10/06/05
Pump test data: Well water was 221 ft. after 12 hours pumping 1600 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 36 in. to 432 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 05 PUB. WTR SUP

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 432 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375
TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 252 ft. to 312 ft.,	From 374 ft. to 426 ft.
	From 326 ft. to 362 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 26 ft. to 88 ft.,	From 178 ft. to 432 ft.
	From 104 ft. to 154 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT BENTONITE BENTONITE
Grout Intervals: From 5 ft. to 26 ft., From 88 ft. to 104 ft., From 154 ft. to 178 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	14	07 FINE SAND 04 SANDY CLAY			
14	24	04 SANDY CLAY			
24	43	05 SAND 11 GRAVEL			
43	50	04 SANDY CLAY 20 LIMESTONE 05 SAND			
50	61	01 CLAY 20 LIMESTONE 05 SAND			
61	110	05 SAND 11 GRAVEL 01 CLAY			
110	117	01 CLAY			
117	128	05 SAND 11 GRAVEL 01 CLAY			
128	138	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/21/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/02/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Chris Reichmuth

1 LOCATION OF WATER WELL: COUNTY: 028 PINNEY	Fraction NE 1/4 SW 1/4 NE 1/4	Section Number 18	Township Number T 25 S	Range Number R 33 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT
 RR#, St. Address, Box # : PO BOX 1078
 City, State, ZIP code : GARDEN CITY, KS 67846-1078

Board of Agriculture, Division of Water Resources
 Application Number: 39984

FROM	TO	LITHOLOGIC LOG
138	151	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
151	166	04 SANDY CLAY 20 LIMESTONE
166	182	05 SAND 13 FINE GRAVEL
182	190	04 SANDY CLAY
190	194	05 SAND 13 FINE GRAVEL
194	200	01 CLAY 20 LIMESTONE
200	231	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
231	233	09 COARSE SAND 15 CRS GRAVEL
233	275	05 SAND 01 CLAY 13 FINE GRAVEL
275	285	07 FINE SAND
285	291	07 FINE SAND 08 MEDIUM SAND 01 CLAY
291	305	01 CLAY 20 LIMESTONE 05 SAND
305	313	01 CLAY 05 SAND
313	325	07 FINE SAND 01 CLAY
325	332	01 CLAY 05 SAND
332	338	07 FINE SAND 01 CLAY
338	351	05 SAND 01 CLAY
351	358	01 CLAY 05 SAND
358	368	07 FINE SAND 01 CLAY
368	383	01 CLAY 05 SAND
383	399	05 SAND 01 CLAY
399	410	07 FINE SAND 01 CLAY
410	413	01 CLAY
413	425	05 SAND 28 ROCK
425	440	23 SANDSTONE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/21/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/02/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Chris Reichmuth