

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 SW 1/4 NW 1/4	Section Number 18	Township Number T 25 S	Range Number R 33 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 6 1/2 MILES SOUTH & 1/2 MILE EAST

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT
RR#, St. Address, Box #: PO BOX 1078
City, State, ZIP code: GARDEN CITY, KS 67846-1078
Board of Agriculture, Division of Water Resources
Application Number: 39986

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	---	NW	---	NE
		X		
M	W	---	---	E
i				
l				
e		SW	---	SE
\ /				

4 DEPTH OF COMPLETED WELL 431 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 186 ft. below land surface measured on mo/day/yr 10/06/05
Pump test data: Well water was 243 ft. after 12 hours pumping 1000 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 36 in. to 431 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 05 PUB. WTR SUP

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 431 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375
TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 202 ft. to 291 ft., From 362 ft. to 374 ft.
	From 318 ft. to 352 ft., From 385 ft. to 425 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 43 ft., From 142 ft. to 431 ft.
	From 61 ft. to 130 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT BENTONITE BENTONITE
Grout Intervals: From 5 ft. to 25 ft., From 43 ft. to 61 ft., From 130 ft. to 142 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	17	07 FINE SAND 01 CLAY			
17	26	04 SANDY CLAY 07 FINE SAND			
26	67	05 SAND 13 FINE GRAVEL 01 CLAY			
67	71	01 CLAY			
71	101	01 CLAY 20 LIMESTONE			
101	115	05 SAND 11 GRAVEL 01 CLAY			
115	135	01 CLAY			
135	141	01 CLAY 05 SAND			
141	153	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/28/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Gene F. Reichmuth

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 SW 1/4 NW 1/4	18	T 25 S	R 33 W

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT
RR#, St. Address, Box # : PO BOX 1078
City, State, ZIP code : GARDEN CITY, KS 67846-1078

Board of Agriculture, Division of Water Resources
Application Number: 39986

FROM	TO	LITHOLOGIC LOG
153	174	01 CLAY
174	178	20 LIMESTONE
178	198	05 SAND 13 FINE GRAVEL
198	204	01 CLAY
204	211	05 SAND 08 MEDIUM SAND 01 CLAY
211	220	04 SANDY CLAY 20 LIMESTONE 05 SAND
220	246	01 CLAY 20 LIMESTONE 05 SAND
246	262	05 SAND 11 GRAVEL 01 CLAY
262	293	05 SAND 13 FINE GRAVEL
293	297	01 CLAY 05 SAND
297	306	07 FINE SAND
306	323	01 CLAY 05 SAND
323	341	07 FINE SAND 01 CLAY
341	350	01 CLAY
350	355	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
355	360	01 CLAY 05 SAND
360	368	01 CLAY
368	384	05 SAND 01 CLAY
384	392	01 CLAY 05 SAND
392	408	05 SAND 01 CLAY
408	411	01 CLAY 05 SAND
411	423	07 FINE SAND
423	440	31 CALICHE 23 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/28/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/05
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Chris J. Kerschmitt*