

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 SE 1/4 SW 1/4	Section Number 18	Township Number T 25 S	Range Number R 33 W
-------------------------------------------------	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 7 MILES SOUTH

2 WATER WELL OWNER: RR#, St. Address, Box # : PO BOX 1078 City, State, ZIP code : GARDEN CITY, KS 67846-1078	WHEATLAND WATER TREATMENT Board of Agriculture, Division of Water Resources Application Number: 39985 20049097
--------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	---		---		---
i	W	---	---	---	E
l		---	---	---	
e		SW	---	SE	---
			X		

4 DEPTH OF COMPLETED WELL 454 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 200 ft. below land surface measured on mo/day/yr 10/01/05
Pump test data: Well water was 238 ft. after 12 hours pumping 1400 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 36 in. to 454 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 05 PUB. WTR SUP

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 454 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375
TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 228 ft. to 328 ft., From 388 ft. to 426 ft.
	From 362 ft. to 378 ft., From 438 ft. to 448 ft.
GRAVEL PACK INTERVALS:	From 40 ft. to 130 ft., From 0 ft. to 0 ft.
	From 144 ft. to 454 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT Bentonite Bentonite
Grout Intervals: From 5 ft. to 25 ft., From 25 ft. to 40 ft., From 130 ft. to 144 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	7	07 FINE SAND 01 CLAY			
7	37	04 SANDY CLAY			
37	57	05 SAND 11 GRAVEL			
57	64	04 SANDY CLAY			
64	100	05 SAND 11 GRAVEL 01 CLAY			
100	133	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
133	138	04 SANDY CLAY			
138	163	05 SAND 11 GRAVEL 01 CLAY			
163	200	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/23/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/19/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 SE 1/4 SW 1/4	Section Number 18	Township Number T 25 S	Range Number R 33 W
-------------------------------------------------	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT
 RR#, St. Address, Box # : PO BOX 1078
 City, State, ZIP code : GARDEN CITY, KS 67846-1078

Board of Agriculture, Division of Water Resources
 Application Number: 39985

FROM	TO	LITHOLOGIC LOG
200	203	01 CLAY
203	211	05 SAND
211	222	01 CLAY 20 LIMESTONE
222	242	05 SAND 11 GRAVEL 01 CLAY
242	259	01 CLAY 20 LIMESTONE 05 SAND
259	266	05 SAND
266	286	04 SANDY CLAY 20 LIMESTONE
286	294	05 SAND 01 CLAY
294	302	01 CLAY
302	313	07 FINE SAND 08 MEDIUM SAND 01 CLAY
313	326	05 SAND 01 CLAY
326	334	01 CLAY
334	351	01 CLAY 20 LIMESTONE
351	356	07 FINE SAND
356	365	01 CLAY 20 LIMESTONE 05 SAND
365	378	07 FINE SAND 01 CLAY
378	386	01 CLAY
386	399	05 SAND 13 FINE GRAVEL
399	404	01 CLAY
404	424	07 FINE SAND 01 CLAY
424	436	01 CLAY 07 FINE SAND
436	445	07 FINE SAND 01 CLAY
445	460	23 SANDSTONE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/23/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/19/05
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richman*