

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SE 1/4 NW 1/4 NW 1/4	31	T 25 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM HOLCOMB; APPX 10 3/4 MILES SOUTH

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT

RR#, St. Address, Box #: PO BOX 1078

Board of Agriculture, Division of Water Resources

City, State, ZIP code: GARDEN CITY, KS 67846-1078

Application Number:

3 LOCATE WELL'S LOCATION WITH

4 DEPTH OF COMPLETED WELL 500ELEVATION: 0

AN "X" IN SECTION BOX:

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \ WELL'S STATIC WATER LEVEL 216 ft. below land surface measured on mo/day/yr 07/29/06

Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

1	NW	NE
M		
i	W	E
l		
e		

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 6 in. to 500 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No ;

\ / If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 2 in. to 500 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 1 lbs/ft. Wall thickness or gauge No. .154

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 230 ft. to 250 ft., From 310 ft. to 330 ft.

From 270 ft. to 290 ft., From 350 ft. to 370 ft.

GRAVEL PACK INTERVALS: From 118 ft. to 500 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 118 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	05 SAND			
1	17	07 FINE SAND			
17	30	01 CLAY 31 CALICHE			
30	43	01 CLAY 31 CALICHE			
43	167	05 SAND 11 GRAVEL			
167	207	05 SAND 11 GRAVEL 01 CLAY			
207	213	01 CLAY			
213	250	05 SAND 13 FINE GRAVEL 01 CLAY			
250	279	01 CLAY 20 LIMESTONE 05 SAND			
279	293	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 07/31/06 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 11/13/06

under the business name of HENKLE DRILLING &amp; SUPPLY

by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SE 1/4 NW 1/4 NW 1/4	31	T 25 S	R 33 W

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT

RR#, St. Address, Box # : PO BOX 1078

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-1078

Application Number:

SCREEN PERFORATED INTERVALS: From 390 ft. to 410 ft., From 470 ft. to 490 ft.  
From 430 ft. to 450 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
293	303	01 CLAY 20 LIMESTONE
303	333	05 SAND 01 CLAY
333	342	01 CLAY 20 LIMESTONE
342	360	01 CLAY 20 LIMESTONE 05 SAND
360	385	01 CLAY
385	424	07 FINE SAND 01 CLAY
424	460	01 CLAY 05 SAND
460	470	23 SANDSTONE 31 CALICHE
470	488	23 SANDSTONE 31 CALICHE
488	500	31 CALICHE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/31/06 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 11/13/06

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Bruce Reichmuth*