

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction SE 1/4 NW 1/4 NE 1/4	Section Number 24	Township Number T 25 S	Range Number R 34 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 7 1/2 MILES SOUTH

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
RR#, St. Address, Box #: PO BOX 430
City, State, ZIP code: HOLCOMB, KS 67851-0430
Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M	W			E
i				
l				
e				
\ /		SW		SE

4 DEPTH OF COMPLETED WELL 420 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 205 ft. below land surface measured on mo/day/yr 5/7-05
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 7/8 in. to 420 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
Blank casing diameter 4 in. to 420 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .337
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS:	From 340 ft. to 420 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 160 ft.,	From 0 ft. to 0 ft.
	From 170 ft. to 420 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 160 ft. to 170 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	05 SAND			
2	5	07 FINE SAND			
5	27	04 SANDY CLAY			
27	45	01 CLAY			
45	63	05 SAND 11 GRAVEL			
63	108	01 CLAY 20 LIMESTONE			
108	119	05 SAND			
119	150	04 SANDY CLAY			
150	159	05 SAND			
159	175	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/22/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction 1/4 1/4 NE 1/4	Section Number 24	Township Number T 25 S	Range Number R 34 W
---	----------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: SUNFLOWER ELECTRIC POWER
RR#, St. Address, Box # : PO BOX 430
City, State, ZIP code : HOLCOMB, KS 67851-0430

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
175	190	01 CLAY
190	221	05 SAND
221	239	05 SAND 20 LIMESTONE
239	260	05 SAND
260	271	01 CLAY
271	316	05 SAND 13 FINE GRAVEL
316	328	04 SANDY CLAY 20 LIMESTONE 05 SAND
328	337	07 FINE SAND 08 MEDIUM SAND 01 CLAY
337	368	04 SANDY CLAY
368	377	05 SAND
377	397	04 SANDY CLAY 05 SAND
397	410	05 SAND 01 CLAY
410	420	31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/22/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Daniel R. Henkle