


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Kearny	Township name Southside	Fraction NW of SE 1/4	Section number 5	Town number T S 25	Range number R W 35		
Distance and direction from nearest town or city: 4 miles south & 3 miles west of Deerfield, Ks. Street address of well location if in city:				3 Owner of well: L.F. Roderick Address: Garden City, Ks. 67846				
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			4 Well depth: 320 ft. Date of completion 1-12-75 Well diameter 26 in.		
2 Type and color of material			From	To	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
			Top Soil, fine to Medium Sand & Gravel (Loose)		0	50	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>	
			Fine to Medium Sand & Gravel streaks of Clay (Loose)		50	95	7 Casing: Material ST Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. 34.25 lbs./ft. 1 16 in. to 321 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No ___ in. to ___ ft. depth	
			Fine to Medium Sand & Gravel (Loose)		95	123	8 Screen: No screen used. Manufacturer _____ Type _____ Dia. _____ Slot/gauze _____ Length _____ Set between _____ ft. and _____ ft. _____ Perforations: 100-200, 280-320 Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 1/2" down	
			Blue Clay with Streaks of Sand & Gravel		123	165	9 Static water level: 60 ft. below land surface Date 1-12-75	
			Fine to Medium Sand & Gravel 15% Clay (Loose)		165	200	10 Pumping level below land surfaces: 108 ft. after 3 hrs. pumping 1227 g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 1200 g.p.m.	
			Sandy Clay streaks of Fine to Medium Sand		200	277	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
			Fine to Medium Sand & Gravel (Loose)		277	320	12 Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade	
			Sandy Clay		320	336	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Clay Puddled Depth: From 0 ft. to 10 ft.	
			Gray Clay		336	350	14 Nearest source of possible contamination: N/A ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Yellow		350	365	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name FMC-Peerless Model number 3028 HP 100 Volts _____ Length of drop pipe 140 ft. capacity 800 g.m.p. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
(use a second sheet if needed)								
16 Remarks: elevation Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley			Good well. Customer well satisfied. No Possible contamination.			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter-Wilson Drlg. Co. 208 Business name _____ License No. _____ Address Box 493 Garden City, Ks. Signed <i>[Signature]</i> Date 2-13-75 Authorized representative		