

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY SW 1/4 NE 1/4 SW 1/4 6 T 25 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 2 3/4 MILES WEST AND 2 3/4 MILES SOUTH OF LAKIN

2 WATER WELL OWNER: WEISEL, INC.  
 RR#, St. Address, Box #: BOX 283 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 160 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 15 ft. below land surface measured on mo/day/yr 06/15/93
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 10 in. to 160 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 01 DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 160 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 110 ft. to 150 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 73 ft., From 0 ft. to 0 ft.  
 From 78 ft. to 160 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 73 ft. to 78 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	19	01 CLAY			
19	60	09 COARSE SAND 14 MED GRAVEL 16 V CRS GRAVEL			
60	97	31 CALICHE 16 V CRS GRAVEL			
97	110	31 CALICHE			
110	150	23 SANDSTONE 31 CALICHE			
150	170	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/15/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/18/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bruce Reichmuth*