

DRILLERS TEST LOG

CUSTOMERS NAME Beymer Water Recreation Park DATE June 16, 1981
STREET ADDRESS % Curtis Reed Box 1136 TEST # 1 E. LOG yes
CITY & STATE Lakin, Kansas 67860 DRILLER Rector
COUNTY Kearny QUARTER NE SECTION 10 TOWNSHIP 25 RANGE 36

LOCATION On West side of sand pit 60' South of shower house

WELL LOCATION

| % | FOOTAGE | | | DESCRIPTION OF STRATA | Static Water Level |
|----|---------|-----|-----|--|--------------------------|
| | From | Pay | To | | Proposed Well Depth 300' |
| | 0 | | 4 | Surface | |
| | 4 | | 46 | Sand, gravel & cobble stones | |
| | 46 | | 60 | Brown clay | |
| | 60 | | 120 | Gray & blue clay (Murky) (Sticky) | |
| | 120 | | 160 | Blue Clay (Sticky) | |
| | 160 | | 190 | Sandy blue clay | |
| | 190 | | 196 | Brown clay | |
| 45 | 196 | 14 | 210 | Sand fine med. coarse, small gravel | |
| | 210 | | 220 | Sand fine med. coarse, clay & lime rock | |
| | 220 | | 230 | Brown clay & lime rock | |
| 20 | 230 | 10 | 240 | Very fine sand & brown sandy clay, hard to catch sand in screen. | |
| 55 | 240 | 20 | 260 | Sand, fine med. coarse, few med. small gravel, few tiny rock and sandy clay stks. | |
| 65 | 260 | 38 | 298 | Sand, fine med. coarse, some med. small gravel some tiny tan rock, real loose used a lot of water. | |
| | 298 | | 300 | Brown clay & soapstone. | |
| | | | | | |
| | | 82 | | | |
| | | | | TOTAL DEPTH 300' | |
| | | | | | 6" Plastic |
| | | | | | Perf. Plain |
| | | | | 300 - 260' | 40' |
| | | | | 260 - 210' | 50' |
| | | | | 210 - 200' | 10' |
| | | | | 200 - 0 | 200' |

GARDEN CITY, KS
Phone 276-3278

BECKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUBINTE, KS
Phone 675-4311

TEST HOLES * * * * * INVESTIGATION & INDUSTRIAL WELLS * * * * * STORAGE WELLS